




# SINGLE-ZONE VERTICAL AIR HANDLING UNIT ENGINEERING MANUAL

Single-Zone Vertical Air Handling Unit System  
18,000 - 48,000 Btu/h



LV180HV4 (18,000 Btu/h)  
LV240HV4 (24,000 Btu/h)



LV360HV4 (36,000 Btu/h)  
LV420HV4 (42,000 Btu/h)  
LV480HV4 (48,000 Btu/h)

## **PROPRIETARY DATA NOTICE**

**This document, as well as all reports, illustrations, data, information, and other materials are the property of LG Electronics U.S.A., Inc., and are disclosed by LG Electronics U.S.A., Inc. only in confidence.  
This document is for design purposes only.**

A summary list of safety precautions is on page 3.

**For more technical materials such as submittals, catalogs, installation, owner's, and service manuals, visit [www.lghvac.com](http://www.lghvac.com).**

# TABLE OF CONTENTS


|                                                         |       |
|---------------------------------------------------------|-------|
| Unit Nomenclature.....                                  | 4     |
| LG Air Conditioner Technical Solution (LATS) .....      | 5-6   |
| Vertical Air Handling Unit Product Data .....           | 7-50  |
| Mechanical Specifications .....                         | 8-9   |
| General Data .....                                      | 10-12 |
| Electrical Data .....                                   | 13    |
| Functions, Controls, and Options .....                  | 14-15 |
| Dimensions .....                                        | 16-19 |
| Acoustic Data .....                                     | 20-30 |
| Refrigerant Flow Diagrams .....                         | 31-32 |
| Wiring Diagrams, Dip Switch Settings .....              | 33-37 |
| Electrical Connections .....                            | 38-42 |
| External Static Pressure and Air Flow Ranges .....      | 43-47 |
| Accessories .....                                       | 48-50 |
| Vertical Air Handling Unit Performance Data .....       | 51-69 |
| Cooling Capacity Data .....                             | 52-56 |
| Heating Capacity Data .....                             | 57-61 |
| Maximum Heating Capacity Data .....                     | 62-66 |
| Equipment Selection Procedure .....                     | 67-69 |
| Vertical Air Handling Unit Application Guidelines ..... | 70-81 |
| Placement Considerations .....                          | 71-74 |
| Clearances .....                                        | 75-77 |
| Installing Outdoor Unit Indoors .....                   | 78-79 |
| Refrigerant Piping Design .....                         | 80-81 |
| Acronyms .....                                          | 82    |

## TABLE OF SYMBOLS

|                                                                                                    |                                                                                                                                |
|----------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------|
|  <b>DANGER</b>  | <i>This symbol indicates an imminently hazardous situation which, if not avoided, will result in death or serious injury.</i>  |
|  <b>WARNING</b> | <i>This symbol indicates a potentially hazardous situation which, if not avoided, could result in death or serious injury.</i> |
|  <b>CAUTION</b> | <i>This symbol indicates a potentially hazardous situation which, if not avoided, may result in minor or moderate injury.</i>  |
| <b>Note:</b>                                                                                       | <i>This symbol indicates situations that may result in equipment or property damage accidents only.</i>                        |
|                 | <i>This symbol indicates an action that should not be performed.</i>                                                           |

# UNIT NOMENCLATURE

## Indoor Units and Outdoor Units





# LG AIR CONDITIONER TECHNICAL SOLUTION (LATS)

## LG Air Conditioner Technical Solution (LATS) Software

A properly designed and installed refrigerant piping system is critical to the optimal performance of LG air-conditioning systems. To assist engineers, LG offers, free of charge, LG Air Conditioner Technical Solution (LATS) software—a total design solution for LG air conditioning systems. Contact your LG Rep for the best software program for your application.

### Note:

To reduce the risk of designing an improper applied system or one that will not operate correctly, LG requires that LATS software be used on all projects.

### Formats

LATS is available to LG customers in three user interfaces: LATS HVAC, LATS CAD2, and LATS Revit. All three LATS formats are available through [www.myLGHVAC.com](http://www.myLGHVAC.com), or contact an LG Sales Representative.

**LATS HVAC** is a Windows®-based application that aids engineers in designing LG Variable Refrigerant Flow (VRF), Multi F / Multi F MAX, Single-Zone, and Energy Recovery Ventilator (ERV) systems.

\*Windows® is a registered mark of Microsoft® Corporation.

**LATS CAD2** combines the LG LATS program with AutoCAD® software\*\*. It permits engineers to layout and validate LG Multi V Variable Refrigerant Flow (VRF), Multi F / Multi F MAX, Single-Zone, and Energy Recovery Ventilator (ERV) systems directly into CAD drawings.

**LATS Revit** integrates the LG LATS program with Revit® software\*\*. It permits engineers to layout and validate Multi V VRF systems directly into Revit drawings.

\*\*AutoCAD® and Revit® are both registered marks of Autodesk, Inc.

### Features

All LG product design criteria have been loaded into the program, making LATS simple to use: double click or drag and drop the component choices. Build systems in Tree Mode where the refrigerant system can be viewed. Switch to a Schematic diagram to see the electrical and communications wiring.

LATS software permits the user to input region data, indoor and outdoor design temperatures, modify humidity default values, zoning, specify type and size of outdoor units and indoor units, and input air flow and external static pressure (ESP) for ducted indoor units.


The program can also:

- Import building loads from a separate Excel file.
- Present options for outdoor unit auto selection.
- Automatically calculate component capacity based on design conditions for the chosen region.
- Verify if the height differences between the various system components are within system limits.
- Provide the correct size of each refrigerant piping segment and LG Y-Branches and Headers.
- Adjust overall piping system length when elbows are added.
- Check for component piping limitations and flag if any parameters are broken.
- Factor operation and capacity for defrost operation.
- Calculate refrigerant charge, noting any additional trim charge.
- Suggest accessories for indoor units and outdoor units.
- Run system simulation.

### Note:

Features depend on which LATS program is being used, and the type of system being designed.

Figure 1: Example of LATS CAD2.



# LG AIR CONDITIONER TECHNICAL SOLUTION (LATS)

## LATS Generates a Complete Project Report

LATS software also generates a report containing project design parameters, cooling and heating design data, system component performance, and capacity data. The report includes system combination ratio and refrigerant charge calculations; and provides detailed bill of material, including outdoor units, indoor units, control devices, accessories, refrigerant pipe sizes segregated by building, by system, by pipe size, and by pipe segments. LATS can generate an Excel GERP report that can imported into the LG SOPS pricing and ordering system.

## Proper Design to Install Procedure

LG encourages a two report design-to-install-procedure. After the design engineer determines building / zone loads and other details, the engineer opens the LATS program and inputs the project's information. When the design is complete, the "Auto Piping" and "System Check" functions should be used to verify piping sizes, limitations, and if any design errors are present. If errors are found, engineers should adjust the design, and run Auto Piping and System Check again. When the design passes the checks, then the engineer prints out a project "Shop Drawing" (LATS Tree Diagram) and provides it to the installing contractor. The contractor should follow the LATS Tree Diagram when building the piping system, but oftentimes the design changes on the building site:


- Architect has changed location and/or purpose of room(s).
- Outdoor unit cannot be placed where originally intended.
- Structural elements prevent routing the piping as planned.
- Air conditioning system conflicts with other building systems (plumbing, gas lines, etc.).

The contractor must mark any deviation from the design on the Shop Drawing, including as-built straight lines and elbows. This "Mark Up" drawing should be returned to the design engineer or Rep, who should input contractor changes into the LATS file. (Copy the original LATS software file, save and rename as a separate file, and modify all piping lengths by double-clicking on each length and editing information.) Like the shop drawing, the Auto Piping and System Check should also be run on this new "As Built" drawing. The design engineer or Rep must then provide the final As Built file to the contractor. The Mark Up version must be compared to the As Built version for:

- Differences in pipe diameter(s). If incorrect diameters have been installed, the piping must be changed out. If pipe diameters have changed, check to see if Y-Branches will also need to be changed.
- Changes to outdoor unit and indoor unit capacities. Capacities changes may impact line length changes.
- Additional refrigerant charge quantity ("Trim Charge"). Trim charge will change if piping lengths and diameters change. The As Built version must reflect installed piping lengths to ensure correct trim charge.

All documents submitted by the contractor, as well as the Shop Drawing and the As Built Drawing files must be provided for commissioning purposes. Model and serial numbers for all system components must also be submitted. If the steps previously detailed are not followed, and all documents are not provided to the commissioning agent, the project runs the risk of not being commissioned and voiding any limited warranty LG offers on the equipment.

Figure 2: Example of a LATS Tree Diagram.



# VERTICAL AIR HANDLING UNIT PRODUCT DATA

**“Mechanical Specifications” on page 8**

**“General Data” on page 10**

**“Electrical Data” on page 13**

**“Functions, Controls, and Options” on page 14**

**“Dimensions” on page 16**

**“Acoustic Data” on page 20**

**“Refrigerant Flow Diagrams” on page 31**

**“Wiring Diagrams” on page 33**

**“Electrical Connections” on page 38**

**“External Static Pressure and Airflow Ranges” on page 43**

**“Accessories” on page 48**

# MECHANICAL SPECIFICATIONS

## Casing

The unit is designed to operate in vertical up flow, down flow (requires conversion kit sold separately), horizontal left, and horizontal right configurations.

Supply air exits from the top and return air enters from the bottom for a vertical up flow configuration. Return air opening is from the top for the vertical down flow configuration. Return air opening is from right end or left end when in horizontal configuration.

The airflow circulation of the supply air and return air is reversed in a vertical down flow configuration. Return air plenum sub-base is to be field provided. Supply air opening has a male flange for duct connection.

The unit case is made of 22-gauge coated metal and the external surfaces are finished with a high gloss baked enamel finish. Finish color is "morning fog" (medium beige). Cold surfaces are galvanized steel.

The cold surfaces of the case are internally insulated with ½ inch foil faced, polystyrene fiber insulation. The inside surface of the fan assembly door access panel is treated with ½ inch polystyrene fiber insulation, encapsulated on both sides, and sealed along the edges with a reinforced foil-faced covering to prevent deterioration caused by panel removal.

All access panels are provided with gasket seals to minimize air leakage. The unit case is designed to accept an internal, optional, LG electric strip heater. The unit bears the ETL label. Unit breaker, fuses, and / or disconnect are provided by others.

## Fan Assembly and Control

The indoor unit has an integral fan assembly consisting of a galvanized steel housing and a forward-curved fan wheel. The direct drive fan/motor assembly is mounted on rubber grommets isolating the rotating assembly from the fan housing. The fan motor is a Brushless Digitally-Controlled design (BLDC), having permanently lubricated and sealed ball bearings. The fan motor includes thermal, overcurrent and low RPM protection. The fan/motor assembly is mounted on vibration attenuating rubber grommets. The fan impeller is statically and dynamically balanced. Fan speed is controlled using a microprocessor-based direct digital control algorithm that provides a minimum of a high fan speed in cooling thermal ON and low fan speed in cooling thermal OFF, high fan speed in heating thermal ON and fan off in heating thermal OFF. The fan speeds can be field adjusted between low, medium, and high speeds and DIP switch settings will allow the fan to run constantly during defrost or oil return modes. Each setting can be field adjusted from the factory setting (RPM/ESP). The setting provides delivery of the high speed air volume against an external static pressure of up to 0.70" in-wg (NJ frame - 18k and 24k), and 1.00" in-wg (NK frame - 36k, 42k, and 48k).

## Air Filter

The unit comes with a filter rack sized to hold a field-provided 16" x 20" x 1" (NJ frame) or 24" x 20" x 1" (NK frame) filter cartridge. The filter rack is equipped with guides that keep the filter centered in the rack. Filter service access is from the front of the unit without removing the coil or fan area access panels. Filter access door is provided with thumb screws that can be removed.

## Optional Auxiliary Electric Heat Module(s)

LG optional electric heat modules are designed for field installation in the reheat position. The electric heat module is provided with heating elements, contractors, relays, high temperature safety switch, and interconnecting control wiring harness with a quick connect plug for easy connection to the air handling unit control board. Auxiliary heat modules are available in nominal capacities of 3, 5, 8, 10, 15, and 20 kW. Heating elements are powered from a field provided separate power source. 3 through 10 kW modules are powered from a single power wire. The 15 and 20 kW modules are powered from two power wires. Heating module breakers, fuses, and / or disconnects are to be field provided.

## Microprocessor Control

The indoor unit is provided with an integrated control panel to communicate with the outdoor unit. All unit operation parameters are stored in non-volatile memory resident on the unit microprocessor. The microprocessor controls space temperature through using the value provided by temperature sensors within the indoor unit. A field-supplied communication cable must be installed to connect the indoor unit(s) to the outdoor unit.

Figure 3: Vertical Air Handling Indoor Unit.



# MECHANICAL SPECIFICATIONS

---

## Controls

The indoor unit is supplied with an LG wired controller. Communication cable from the outdoor unit to the indoor unit must be a minimum of 18 AWG, four (4) conductor, shielded or unshielded (if shielded, must be grounded to chassis at ODU only) and must comply with applicable local and national codes.

## Condensate

The unit is designed for gravity draining of condensate.

## Condensate Drain Pan

The condensate drain pan is constructed of HIPS (high impact polystyrene resin).

## Coil

The indoor unit coil is constructed with grooved design copper tubes with slit coil fins, 3 rows, 18 fins per inch.

## Controls Features

- Inverter (Variable speed fan)
- Child lock function
- Auto changeover
- Auto restart operation
- Dehumidifying function
- Two thermistor control
- Group control
- External static pressure control
- Self-diagnostics function
- Wired thermostat included

## Vertical Down Flow Configuration

NJ and NK frames come factory configured for vertical up flow. Down flow configuration requires a conversion kit sold separately (model numbers: PNDFJ0 for NJ frame and PNDFK0 for NK frame). The kit contains support brackets for the evaporator coil/drain pan subassembly, addition screws, and a replace front panel to accommodate the coil and drain connections for down flow configuration.

# GENERAL DATA

## Pairing Table

Table 1: Single Zone Vertical Air Handling Unit Pairing Table

| Outdoor Unit Model                                                                                                      | Indoor Unit Model                                                                                                                  | Remote Controller                                                                                                                                                                                                                                    |
|-------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| LUU188HV<br>LUU248HV<br>               | LVN180HV4, LVN240HV4 (NJ frame)<br>              | PQRCVCL0QW (LG supplied, wired)<br><br>PQWRHQ0FDB (Optional, wireless)<br>    |
| LUU368HV<br>LUU428HV<br>LUU488HV<br> | LVN360HV4, LVN420HV, LVN480HV<br>(NK frame)<br> | PQRCVCL0QW (LG supplied, wired)<br><br>PQWRHQ0FDB (Optional, wireless)<br> |



# GENERAL DATA / SPECIFICATIONS

Table 2: Vertical Air Handling Unit General Data.

| Type                                        | Vertical Air Handling Unit           |                                      |                                      |                                    |                                    |
|---------------------------------------------|--------------------------------------|--------------------------------------|--------------------------------------|------------------------------------|------------------------------------|
| System (Model) (Indoor Unit / Outdoor Unit) | LV180HV4<br>(LVN180HV4/<br>LUU188HV) | LV240HV4<br>(LVN240HV4/<br>LUU248HV) | LV360HV4<br>(LVN360HV4/<br>LUU368HV) | LV420HV<br>(LVN420HV/<br>LUU428HV) | LV480HV<br>(LVN480HV/<br>LUU488HV) |
| Cooling Capacity (Min/Rated/Max) (Btu/h)    | 8,000 ~ 18,000 ~ 24,000              | 9,000 ~ 24,000 ~ 28,000              | 14,000 ~ 36,000 ~ 44,000             | 17,000 ~ 42,000 ~ 48,000           | 18,000 ~ 48,000 ~ 53,000           |
| Cooling Power Input¹ (kW)                   | 0.65 ~ 1.35 ~ 2.70                   | 0.70 ~ 1.92 ~ 3.20                   | 1.25 ~ 2.88 ~ 4.80                   | 1.35 ~ 3.80 ~ 5.30                 | 1.40 ~ 4.80 ~ 6.00                 |
| EER                                         | 13.33                                | 12.50                                | 12.50                                | 11.05                              | 10.00                              |
| SEER                                        | 19.0                                 | 18.0                                 | 18.0                                 | 17.0                               | 16.5                               |
| Heating Capacity (Min/Rated/Max) (Btu/h)    | 9,000 ~ 20,000 ~ 23,000              | 10,000 ~ 27,000 ~ 30,000             | 15,000 ~ 40,000 ~ 47,000             | 18,000 ~ 47,000 ~ 55,000           | 19,000 ~ 56,000 ~ 60,000           |
| Heating Power Input¹ (kW)                   | 0.65 ~ 1.60 ~ 2.10                   | 0.75 ~ 2.26 ~ 2.80                   | 1.35 ~ 3.39 ~ 5.05                   | 1.45 ~ 4.00 ~ 5.65                 | 1.50 ~ 5.10 ~ 6.20                 |
| COP                                         | 3.66                                 | 3.50                                 | 3.46                                 | 3.44                               | 3.22                               |
| HSPF                                        | 9.5                                  | 10.0                                 | 10.0                                 | 10.0                               | 9.5                                |
| Maximum Heating Capacity (Btu/h)            |                                      |                                      |                                      |                                    |                                    |
| Outdoor 17°F) (WB)/Indoor 70°F (DB)         | 18,000                               | 22,000                               | 32,000                               | 37,000                             | 40,000                             |
| Outdoor 5°F(WB)/Indoor 70°F (DB)            | 16,000                               | 20,000                               | 30,000                               | 32,000                             | 34,000                             |
| Power Input [W] @ Outdoor 5°F (WB)          | 2,500                                | 3,200                                | 4,400                                | 4,800                              | 5,250                              |
| Outdoor -4 °F(WB)/Indoor 70°F (DB)          | 11,000                               | 15,000                               | 22,000                               | 24,000                             | 26,000                             |
| Power Supply V, Ø, Hz                       | 208-230 / 1 / 60                     |                                      | 208-230 / 1 / 60                     |                                    |                                    |
| Outdoor Unit Operating Range                |                                      |                                      |                                      |                                    |                                    |
| Cooling (°F DB)                             | 5 - 118                              | 5 - 118                              | 5 - 118                              | 5 - 118                            | 5 - 118                            |
| Optional Wind Baffle Cooling (°F DB)        | Yes(-4)                              | Yes(-4)                              | Yes(-4)                              | Yes(-4)                            | Yes(-4)                            |
| Heating (°F WB)                             | -4 - 64                              | -4 - 64                              | -4 - 64                              | -4 - 64                            | -4 - 64                            |
| Indoor Unit Operating Range                 |                                      |                                      |                                      |                                    |                                    |
| Cooling (°F WB)                             | 57-77                                | 57-77                                | 57-77                                | 57-77                              | 57-77                              |
| Heating (°F DB)                             | 59-81                                | 59-81                                | 59-81                                | 59-81                              | 59-81                              |
| Indoor Temperature Setting Range            |                                      |                                      |                                      |                                    |                                    |
| Cooling (°F DB)                             | 65-86                                | 65-86                                | 65-86                                | 65-86                              | 65-86                              |
| Heating (°F WB)                             | 61-86                                | 61-86                                | 61-86                                | 61-86                              | 61-86                              |

EEV: Electronic Expansion Valve, IDU: Indoor Unit, ODU: Outdoor Unit. This unit comes with a dry helium charge.  
This data is rated 0 ft above sea level, with 24.6 ft of refrigerant line per indoor unit and a 0 ft level difference between outdoor and indoor units.

Cooling capacity rating obtained with air entering the indoor coil at 80°F dry bulb (DB) and 67°F wet bulb (WB); and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

Heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB); and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

1 Power Input is rated at high speed.

2 Power wiring to the outdoor unit must be solid or stranded, and must comply with the applicable local and national electric codes.

Communication cable from the outdoor unit to the indoor unit must be a minimum of 18 AWG, four (4) conductor, shielded or unshielded (if shielded, must be grounded to chassis at ODU only) and must comply with applicable local and national codes.

3 Take appropriate actions at the end of HVAC equipment life to recover, recycle, reclaim or destroy R410A refrigerant according to applicable regulations (40 CFR Part 82, Subpart F) under section 608 of CAA.

4 Sound pressure levels are tested in an anechoic chamber under ISO Standard 3745 and are the same in both cooling and heating mode. These values can increase due to ambient conditions during operation.

5 Piping lengths are equivalent.

# GENERAL DATA / SPECIFICATIONS

Table 3: Vertical Air Handling Unit General Data, continued.

| Type                                                                  | Vertical Air Handling Unit              |                                      |                                         |                                    |                                    |
|-----------------------------------------------------------------------|-----------------------------------------|--------------------------------------|-----------------------------------------|------------------------------------|------------------------------------|
| System (Model) (Indoor Unit / Outdoor Unit)                           | LV180HV4<br>(LVN180HV4/<br>LUU188HV)    | LV240HV4<br>(LVN240HV4/<br>LUU248HV) | LV360HV4<br>(LVN360HV4/<br>LUU368HV)    | LV420HV<br>(LVN420HV/<br>LUU428HV) | LV480HV<br>(LVN480HV/<br>LUU488HV) |
| Unit Data                                                             |                                         |                                      |                                         |                                    |                                    |
| Refrigerant Type <sup>3</sup>                                         | R410A                                   | R410A                                | R410A                                   | R410A                              | R410A                              |
| Additional Refrigerant Charge (oz./ft.)                               | 0.43                                    | 0.43                                 | 0.43                                    | 0.43                               | 0.43                               |
| Refrigerant Control                                                   | EEV                                     | EEV                                  | EEV                                     | EEV                                | EEV                                |
| Indoor Unit Sound Pressure Level (dB(A))<br>(H/M/L) <sup>4</sup>      | 42 / 42 / 41                            | 43 / 42 / 41                         | 45 / 44 / 43                            | 48 / 45 / 44                       | 49 / 48 / 44                       |
| Outdoor Unit Sound Pressure Level (dB(A))<br>(Cool/Heat) <sup>4</sup> | 48 / 52                                 | 48 / 52                              | 52 / 54                                 | 52 / 54                            | 52 / 54                            |
| Indoor Unit Net / Shipping Weight (lbs.)                              | 129 / 140                               | 129 / 140                            | 165 / 188                               | 165 / 188                          | 165 / 188                          |
| Outdoor Unit Net / Shipping Weight (lbs.)                             | 129 / 141                               | 129 / 141                            | 203 / 232                               | 203 / 232                          | 203 / 232                          |
| Power Wiring / Communications Cable (No. x AWG) <sup>2</sup>          | 4 x 18                                  | 4 x 18                               | 4 x 18                                  | 4 x 18                             | 4 x 18                             |
| Power Supply (No. x AWG)                                              | 3 x 12                                  | 3 x 12                               | 3 x 10                                  | 3 x 10                             | 3 x 10                             |
| Compressor (Type x Qty.)                                              | Twin Rotary x 1                         | Twin Rotary x 1                      | Twin Rotary x 1                         | Twin Rotary x 1                    | Twin Rotary x 1                    |
| Dehumidification Rate (pts./hr.)                                      | 2                                       | 2.5                                  | 3.4                                     | 4.3                                | 5.2                                |
| Fan                                                                   |                                         |                                      |                                         |                                    |                                    |
| Indoor Unit Type x Qty.                                               | Sirocco x 1                             | Sirocco x 1                          | Sirocco x 1                             | Sirocco x 1                        | Sirocco x 1                        |
| Outdoor Unit Type x Qty.                                              | Propeller x 1                           | Propeller x 1                        | Propeller x 2                           | Propeller x 2                      | Propeller x 2                      |
| Motor / Drive                                                         | Brushless Digitally Controller / Direct |                                      | Brushless Digitally Controlled / Direct |                                    |                                    |
| Airflow Rate                                                          |                                         |                                      |                                         |                                    |                                    |
| Indoor Unit (H / M / L [CFM])                                         | 640 / 580 / 480                         | 710 / 640 / 480                      | 1,100 / 1,000 / 900                     | 1,260 / 1,100 / 1,000              | 1,400 / 1,260 / 1,000              |
| Outdoor Unit (CFM)                                                    | 2,048                                   | 2,048                                | 1,942 x 2                               | 1,942 x 2                          | 1,942 x 2                          |
| Factory Set (High) External Static Pressure (in.wg)                   | 0.3                                     | 0.3                                  | 0.3                                     | 0.3                                | 0.3                                |
| Piping                                                                |                                         |                                      |                                         |                                    |                                    |
| Liquid (in.)                                                          | 3/8                                     | 3/8                                  | 3/8                                     | 3/8                                | 3/8                                |
| Vapor (in.)                                                           | 5/8                                     | 5/8                                  | 5/8                                     | 5/8                                | 5/8                                |
| Indoor Unit Condensate Drain I.D. (in.)                               | Primary & Sec-<br>ondary: 3/4 FPT       | Primary & Sec-<br>ondary: 3/4 FPT    | Primary & Sec-<br>ondary: 3/4 FPT       | Primary & Sec-<br>ondary: 3/4 FPT  | Primary & Sec-<br>ondary: 3/4 FPT  |
| Maximum Pipe Length (ft.) <sup>5</sup>                                | 164                                     | 164                                  | 246                                     | 246                                | 246                                |
| Piping Length (no additional refrigerant, ft.)                        | 24.6                                    | 24.6                                 | 24.6                                    | 24.6                               | 24.6                               |
| Maximum Elevation Difference (ft.)                                    | 98.4                                    | 98.4                                 | 98.4                                    | 98.4                               | 98.4                               |

EEV: Electronic Expansion Valve, IDU: Indoor Unit, ODU: Outdoor Unit. This unit comes with a dry helium charge.

This data is rated 0 ft above sea level, with 24.6 ft of refrigerant line per indoor unit and a 0 ft level difference between outdoor and indoor units.

Cooling capacity rating obtained with air entering the indoor coil at 80°F dry bulb (DB) and 67°F wet bulb (WB); and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB). Heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB); and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

1 Power Input is rated at high speed.

2 Power wiring to the outdoor unit must be solid or stranded, and must comply with the applicable local and national electric codes.

Communication cable from the outdoor unit to the indoor unit must be a minimum of 18 AWG, four (4) conductor, shielded or unshielded (if shielded, must be grounded to chassis at ODU only) and must comply with applicable local and national codes.

3 Take appropriate actions at the end of HVAC equipment life to recover, recycle, reclaim or destroy R410A refrigerant according to applicable regulations (40 CFR Part 82, Subpart F) under section 608 of CAA.

4 Sound pressure levels are tested in an anechoic chamber under ISO Standard 3745 and are the same in both cooling and heating mode. These values can increase due to ambient conditions during operation.

5 Piping lengths are equivalent.



## Electrical Data

Table 4: Vertical Air Handling Unit ODU Electrical Data.

| Nominal Tons | Model Name | Unit |         |                        | Power Supply |     | Compressor Quantity | Compressor Motor RLA (Cooling) | Condenser Fan Motor(s)  |                         |
|--------------|------------|------|---------|------------------------|--------------|-----|---------------------|--------------------------------|-------------------------|-------------------------|
|              |            | Hz   | Volts   | Voltage Range          | MCA          | MOP |                     |                                | Condenser Fan Quantity. | Condenser Fan Motor FLA |
| 1.5          | LUU188HV   | 60   | 208/230 | Min.: 187<br>Max.: 253 | 20           | 30  | 1                   | 13.5                           | 1                       | 1.6                     |
| 2.0          | LUU248HV   |      |         |                        | 20           | 30  | 1                   | 13.5                           | 1                       | 1.6                     |
| 3.0          | LUU368HV   |      |         |                        | 32           | 40  | 1                   | 21.0                           | 2                       | 1.6 x 2                 |
| 3.5          | LUU428HV   |      |         |                        | 32           | 40  | 1                   | 21.0                           | 2                       | 1.6 x 2                 |
| 4.0          | LUU488HV   |      |         |                        | 32           | 40  | 1                   | 21.0                           | 2                       | 1.6 x 2                 |

Voltage tolerance is  $\pm 10\%$ .

Maximum allowable voltage unbalance is 2%.

RLA = Rated Load Amps.

MCA = Minimum Circuit Ampacity.

Maximum Overcurrent Protection (MOP) is calculated as follows:  
(Largest motor FLA x 2.25) + (Sum of other motor FLA) rounded down to the nearest standard fuse size.

# FUNCTIONS, CONTROLS, AND OPTIONS

## Indoor Unit

### Functions, Controls, and Options for LVN180HV4, LVN240HV4, LVN360HV4, LVN420HV, LVN480HV

Table 5: Indoor Unit—Functions, Controls and Options.

| Indoor Unit Type |                                                                                                             | Vertical Air Handling Unit |
|------------------|-------------------------------------------------------------------------------------------------------------|----------------------------|
| Airflow          | Air Supply Outlet                                                                                           | 1                          |
|                  | Airflow steps (fan/cool/heat)                                                                               | 3/3/3                      |
|                  | Washable anti-fungal <sup>1</sup>                                                                           | X                          |
| Operation        | Drain pump                                                                                                  | X                          |
|                  | E.S.P Control                                                                                               | √                          |
|                  | Hot Start                                                                                                   | √                          |
|                  | Self diagnostics                                                                                            | √                          |
|                  | Soft Dry (dehumidification)                                                                                 | √                          |
|                  | Auto changeover                                                                                             | √                          |
|                  | Auto restart                                                                                                | √                          |
|                  | Child lock                                                                                                  | o                          |
|                  | Group control – Requires the use of one Group Control Cable Kit (PZCWRCG3) for every additional indoor unit | o                          |
|                  | Sleep mode                                                                                                  | √                          |
|                  | Timer (on/off)                                                                                              | √                          |
|                  | Weekly schedule                                                                                             | √                          |
|                  | Two thermistor control                                                                                      | o                          |
| Controllers      | 7-Day programmable controller                                                                               | o                          |
|                  | Simple wired remote controller                                                                              | √                          |
|                  | Wireless LCD remote control                                                                                 | o <sup>2</sup>             |
|                  | Dry contact                                                                                                 | √                          |
|                  | Dry contact (temperature setting)                                                                           | X                          |
|                  | Central control (LGAP)                                                                                      | √                          |

<sup>1</sup>Primary washable filters.

<sup>2</sup>Requires wired zone controller.

√ = Standard feature

o = Unit option

X = Not Available

# FUNCTIONS, CONTROLS, AND OPTIONS

Outdoor Unit

## Functions, Controls, and Options for LUU188HV, LUU248HV, LUU368HV, LUU428HV, LUU488HV

Table 6: Outdoor Unit—Functions, Controls and Options.

| Outdoor Unit         |                                      |            |            |            |            |            |
|----------------------|--------------------------------------|------------|------------|------------|------------|------------|
| Category             | Functions                            | LUU188HV   | LUU248HV   | LUU368HV   | LUU428HV   | LUU488HV   |
| Reliability          | Defrost / Deicing                    | O          | O          | O          | O          | O          |
|                      | High pressure sensor                 | O          | O          | O          | O          | O          |
|                      | Phase protection                     | X          | X          | X          | X          | X          |
|                      | Restart delay (3-minutes)            | O          | O          | O          | O          | O          |
|                      | Self diagnosis                       | O          | O          | O          | O          | O          |
|                      | Soft start                           | O          | O          | O          | O          | O          |
| Convenience          | Night Quiet Operation                | O          | O          | O          | O          | O          |
|                      | Mode Lock                            | O          | O          | O          | O          | O          |
|                      | Pump Down (Forced Cooling Operation) | O          | O          | O          | O          | O          |
|                      | Network solution (LGAP)              | O          | O          | O          | O          | O          |
| Central Controller   | AC Smart IV                          | PACS4B000  | PACS4B000  | PACS4B000  | PACS4B000  | PACS4B000  |
|                      | ACP IV                               | PACP4B000  | PACP4B000  | PACP4B000  | PACP4B000  | PACP4B000  |
|                      | PI485                                | PMNFP14A1  | PMNFP14A1  | PMNFP14A1  | PMNFP14A1  | PMNFP14A1  |
| Remote Controller    | MultiSITE CRC1                       | PREMTBVC0  | PREMTBVC0  | PREMTBVC0  | PREMTBVC0  | PREMTBVC0  |
|                      | MultiSITE CRC1+                      | PREMTBVC1  | PREMTBVC1  | PREMTBVC1  | PREMTBVC1  | PREMTBVC1  |
| Integration Solution | MultiSITE Communications Manager     | PBACNBTR0A | PBACNBTR0A | PBACNBTR0A | PBACNBTR0A | PBACNBTR0A |

√ = Standard feature

O = Unit option


X = Not Available

# OUTDOOR UNIT DIMENSIONS

LUU188HV, LUU248HV

## Dimensions for LUU188HV, LUU248HV

Figure 4: LUU188HV, LUU248HV Unit Dimensions.




# OUTDOOR UNIT DIMENSIONS

## LUU368HV, LUU428HV, LUU488HV

### Dimensions for LUU368HV, LUU428HV, LUU488HV

Figure 5: LUU368HV, LUU428HV, LUU488HV Unit Dimensions.




# INDOOR UNIT DIMENSIONS

LVN180HV4, LVN240HV4

## Dimensions for LVN180HV4, LVN240HV4 (NJ frame)

Figure 6: LVN180HV4, LVN240HV4 Indoor Unit Dimensions.



Unit: inches


Note: All measurements have a tolerance of  $\pm 1/4$  in.

# INDOOR UNIT DIMENSIONS

LVN360HV4, LVN420HV, LVN480HV

## Dimensions for LVN360HV4, LVN420HV, LVN480HV (NK frame)

Figure 7: LVN360HV4, LVN420HV, LVN480HV Indoor Unit Dimensions.






# ACOUSTIC DATA

## Indoor Units

### Indoor Unit Sound Pressure Measurement

Figure 8: Sound Pressure Measurement Location.



- Measurements are taken 3.3 ft away from the front of the unit.
- Sound pressure levels are measured in dB(A) with a tolerance of  $\pm 3$ .
- Sound pressure levels are tested in an anechoic chamber under ISO Standard 3745.

Operating Conditions:

- Power source: 220V/60 Hz
- Sound level will vary depending on a range of factors including the construction (acoustic absorption coefficient) of a particular room in which the unit was installed.

### Indoor Unit Sound Pressure Levels

Table 7: Vertical Air Handling Unit Indoor Unit Sound Pressure Levels.



| Model            | Sound Pressure Levels dB(A) |                  |               |
|------------------|-----------------------------|------------------|---------------|
|                  | High Fan Speed              | Medium Fan Speed | Low Fan Speed |
| <i>NJ Frames</i> |                             |                  |               |
| LVN180HV4        | 42                          | 42               | 41            |
| LVN240HV4        | 43                          | 42               | 41            |
| <i>NK Frames</i> |                             |                  |               |
| LVN360HV4        | 45                          | 44               | 43            |
| LVN420HV         | 48                          | 45               | 44            |
| LVN480HV         | 49                          | 48               | 44            |

LVN180HV4, LVN240HV4 Sound Pressure Diagrams

Figure 9: LVN180HV4 and LVN240HV4 Sound Pressure Level Diagrams.

LVN180HV4

LVN240HV4




# ACOUSTIC DATA

## Indoor Units


### LVN360HV4, LVN420HV Sound Pressure Diagrams

Figure 10: LVN360HV4 and LVN420HV Sound Pressure Level Diagrams.

LVN360HV4




LVN420HV



LVN480HV Sound Pressure Diagrams

Figure 11: LVN480HV Sound Pressure Level Diagrams.



# ACOUSTIC DATA

## Indoor Units

### Sound Power Levels


Table 8: Vertical Air Handling Unit Sound Power Levels.

| Model            | Sound Power Levels dB(A) |
|------------------|--------------------------|
|                  | High Fan Speed           |
| <b>NJ Frames</b> |                          |
| LVN180HV4        | 59                       |
| LVN240HV4        | 60                       |
| <b>NK Frames</b> |                          |
| LVN360HV4        | 61                       |
| LVN420HV         | 61                       |
| LVN480HV         | 62                       |

- Data is valid under diffuse field conditions.
- Data is valid under nominal operating conditions.
- Sound power level is measured using rated conditions, and tested in a reverberation room per ISO 3741 standards.
- Sound level will vary depending on a range of factors such as construction (acoustic absorption coefficient) of particular area in which the equipment is installed.
- Reference acoustic intensity: 0dB = 10E-6μW/m<sup>2</sup>


### Sound Power Level Diagrams for LVN180HV4 and LVN240HV4

Figure 12: LVN180HV4 and LVN240HV4 Sound Power Level Diagrams.



Sound Power Level Diagrams for LVN360HV4 and LVN420HV

Figure 13: LVN360HV4 and LVN420HV Sound Power Level Diagrams.




# ACOUSTIC DATA

Indoor Units

## Sound Power Level Diagram for LVN480HV


Figure 14: LVN480HV Sound Power Level Diagram.





Outdoor Unit Sound Pressure Level Measurement

Figure 15: Vertical Air Handling Unit Outdoor Unit Sound Pressure Level Measurement Location.



- Measurements taken with no attenuation and units operating at full load normal operating condition.
- Sound level will vary depending on a range of factors such as construction (acoustic absorption coefficient) of particular area in which the equipment is installed.
- Sound power levels are measured in dB(A)±3.
- Tested in anechoic chamber per ISO Standard 3745.

Outdoor Unit Sound Pressure Levels

Table 9: Vertical Air Handling Unit Outdoor Unit Sound Pressure Levels (dB[A]).

| Outdoor Unit |                              |         |
|--------------|------------------------------|---------|
| Model        | Sound Pressure Level [dB(A)] |         |
|              | Cooling                      | Heating |
| LUU188HV     | 48                           | 52      |
| LUU248HV     | 48                           | 52      |
| LUU368HV     | 52                           | 54      |
| LUU428HV     | 52                           | 54      |
| LUU488HV     | 52                           | 54      |



# ACOUSTIC DATA

## Outdoor Units

### Outdoor Unit Sound Pressure Diagrams

Figure 16: LUU188HV , LUU248HV Sound Pressure Level Diagram.





Figure 17: LUU368HV, LUU428HV, LUU488HV Sound Pressure Level Diagram.




## Outdoor Unit Sound Power Levels

Table 10: Vertical Air Handling Unit ODU Sound Power Levels.

| Model    | Sound Power Levels dB(A) |
|----------|--------------------------|
|          | Max                      |
| LUU188HV | 67                       |
| LUU248HV | 68                       |
| LUU368HV | 66                       |
| LUU428HV | 67                       |
| LUU488HV | 68                       |

## Sound Power Level Diagrams for LUU188HV, LUU248HV

Figure 18: LUU188HV , LUU248HV Sound Power Level Diagrams.




# ACOUSTIC DATA

## Outdoor Units

### Sound Power Level Diagrams for LUU368HV, LUU428HV, LUU488HV

Figure 19: LUU368HV , LUU428HV, LUU488HV Sound Power Level Diagrams.



# REFRIGERANT FLOW DIAGRAM

Indoor Units

## Refrigerant Flow Diagrams for LVN180HV4, LVN240HV4, LVN360HV4, LVN-420HV, LVN480HV

Figure 20: Indoor Unit Refrigerant Flow Diagrams.




Table 11: NJ, NK Frame Refrigerant Pipe Connection Port Diameters.

| Model     | Liquid (inch) | Vapor (inch) |
|-----------|---------------|--------------|
| NJ Frames |               |              |
| LVN180HV4 | 3/8           | 5/8          |
| LVN240HV4 |               |              |
| NK Frames |               |              |
| LVN360HV4 | 3/8           | 5/8          |
| LVN420HV  |               |              |
| LVN480HV  |               |              |

# REFRIGERANT FLOW DIAGRAM

## Outdoor Units

### Refrigerant Flow Diagrams for LUU188HV, LUU248HV, LUU368HV, LUU428HV, LUU488HV

Figure 21: LUU188HV, LUU248HV, LUU368HV, LUU428HV, LUU488HV Refrigerant Flow Diagrams.





Table 12: Vertical Air Handling Unit ODU LUU188~488HV Thermistor Details.

| Description (Based on Cooling Mode)        | PCB Connector |        |
|--------------------------------------------|---------------|--------|
|                                            |               |        |
| Suction Temperature Thermistor             | CN-TH3        | CN-TH3 |
| Discharge Temperature Thermistor           |               | CN-TH3 |
| Condenser Outlet Temperature Thermistor    | CN-TH2        | CN-TH2 |
| Outdoor Ambient Air Temperature Thermistor |               | CN-TH2 |
| Condenser Inlet Temperature Thermistor     | CN-TH4        | CN-TH4 |

# INDOOR UNIT WIRING DIAGRAM

## LVN180HV4, LVN240HV4, LVN360HV4, LVN420HV, LVN480HV

Figure 22: Indoor Unit Wiring Diagrams.




| MODEL           | Fuse             |
|-----------------|------------------|
| 180 / 240       | 250 V / T 3.15 A |
| 360 / 420 / 480 | 250 V / T 5 A    |

# OUTDOOR UNIT WIRING DIAGRAM

## LUU188HV, LUU248HV


Figure 23: Outdoor Unit LUU188HV, LUU248HV Wiring Diagrams.



# OUTDOOR UNIT WIRING DIAGRAM

## LUU368HV, LUU428HV, LUU488HV

Figure 24: Outdoor Unit LUU368HV, LUU428HV, LUU488HV Wiring Diagrams.





# ELECTRICAL WIRING

## NJ/NK Frame Wiring Diagram Legend

Table 13: NJ/NK Frame Wiring Diagram Legend.

| Terminal         | Purpose                      | Function                                |
|------------------|------------------------------|-----------------------------------------|
| CN-POWER         | AC Power supply              | AC Power line                           |
| CN-MOTOR1        | Fan motor output             | Motor output of BLDC                    |
| CN_OUT           | Heater                       | Connection for heater                   |
| CN-D/PUMP        | Drain pump output            | AC output for drain pump                |
| CN-FLOAT         | Float switch input           | Float switch sensing                    |
| CN-ZONE          | Zone controller              | Zone controller connection              |
| CN-OPTION        | Optional PCB EPROM           | Option PCB connection                   |
| CN-EXT           | External ON / OFF controller | External ON / OFF controller connection |
| CN-DISPLAY       | Display                      | Display of indoor status                |
| CN-CC            | Dry contact                  | Dry Contact connection                  |
| CN-PIPE/OUT (RD) | Discharge pipe sensor        | Pipe out thermistor                     |
| CN-LEAK (VI)     | Refrigerant leak detector    | Refrigerant leak detector connection    |
| CN-PIPE/IN (WH)  | Suction pipe sensor          | Pipe in thermistor                      |
| CN-REMO (GN)     | Wired remote controller      | Wired remote control connection         |
| CN-ROOM (YL)     | Room sensor                  | Room air thermistor                     |
| CN-DAMPER        | Damper Controller            | Damper connection                       |
| CN-AIRC          | Air Cleaner                  | Air Cleaner connection                  |
| CN-WF            | Wifi                         | Wifi Module connection                  |

# ELECTRICAL WIRING

## Dip Switch Settings

### Dip Switch Settings for Indoor Unit PCB

Table 14: NJ/NK Frame DIP Switch Settings.

| Dip Switch | Function         | Off           | On    | Description                                                                                                                                                                                                                                                                                                                                   |
|------------|------------------|---------------|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SW1        | COMMUNICATION    | Off (default) | –     | –                                                                                                                                                                                                                                                                                                                                             |
| SW2        | CYCLE            | Off (default) | –     | –                                                                                                                                                                                                                                                                                                                                             |
| SW3        | GROUP CONTROL    | Master        | Slave | Group control setting using 7-Day Programmable Controller; selects Master/Slave on each indoor unit.                                                                                                                                                                                                                                          |
| SW4        | DRY CONTACT MODE | Variable      | Auto  | Sets operation mode for optional Dry Contact accessory.<br>1. Variable: Auto or Manual Mode can be set through 7-Day Programmable Controller or Wireless Remote Controller (factory default setting is Auto if there is no setting).<br>2. Auto: For Dry Contact, it is always Auto mode.                                                     |
| SW5        | CONTINUOUS FAN   | Off           | On    | Selects continuous fan for ducted indoor units.<br>1. On: Indoor unit fan will always operate at a set fan speed, except when the system is off, or the outdoor unit is in defrost mode (when the outdoor unit is in defrost mode, the fan will operate at super low fan speed).<br>2. Off: Indoor unit fan speed can be changed by on / off. |
| SW6        | HEATER INTERLOCK | Off           | On    | Selects heater interlock function for Vertical Air Handling units.<br>1. On: Automatic (heater will automatically operate during heating mode).<br>2. Off: Manual (heater needs to be manually turned on during heating mode).                                                                                                                |
| SW7        | Off              |               |       |                                                                                                                                                                                                                                                                                                                                               |
| SW8        | Off              |               |       |                                                                                                                                                                                                                                                                                                                                               |

### Note:

To operate the indoor unit without Internal Electric Heater, Dip switch 1, 2, 6, 8 must be set OFF.

To operate the indoor unit with Internal Electric heater, Dip switch 6 must be set ON.

- SW6 ON: Automatic Heater operation: Heater operates automatically.
- SW6 OFF: Manual Heater operation: Owner's involvement is required for on/off operation.

If you operate the indoor unit with Internal Electric heater with Dip switch 5, note the following:

- SW5 ON: Fan operates continuously. During defrosting or oil return operation, uninterrupted heating can be attained, as a result of continuous heater and fan operation.
- SW5 OFF: Fan discontinuous operation. There would be reduction in heating capacity while defrosting or oil return operation.

# ELECTRICAL CONNECTIONS

## General Power Wiring / Communications Cable Guidelines

- Follow manufacturer's circuit diagrams displayed on the inside of the control box cover.
- Have a separate power supply for the indoor units.
- Provide a circuit breaker switch between the power source and the indoor unit.
- Confirm power source specifications.
- Properly ground the outdoor unit and the indoor unit per NEC and local codes.
- Connect the wiring firmly so that the wires cannot be easily pulled out.
- Confirm that the electrical capacity is sufficient.
- Power supply to the outdoor unit must be selected based on NEC and local codes. Maximum allowable voltage fluctuation  $\pm 10\%$  or name-plate rated value.
- It is recommended that a circuit breaker is installed, especially if conditions could become wet or moist.
- Include a disconnect in the power wiring system. Add an air gap contact separation of at least 1/8 inch in each active (phase) conductor.
- Any openings where the field wiring enters the cabinet must be completely sealed.

⊘ Do not install power wiring to the outdoor unit and the communication / connection (power) cable to the indoor unit in the same conduit. Use separate conduits.

## Power Wiring / Communications Cable Specifications

- Power wiring to the outdoor unit must be solid or stranded, and must comply with the applicable local and national electric codes.
- Communication cable from the outdoor unit to the indoor unit must be a minimum of 18 AWG, four (4) conductor, shielded or unshielded (if shielded, must be grounded to chassis at ODU only) and must comply with applicable local and national codes.
- Communication cable from indoor unit to remote controller(s) is to be 22 AWG, 3-conductor, twisted, stranded, unshielded. Wiring must comply with all applicable local and national codes.

### WARNING

- Terminal screws may become loose during transport. Properly tighten the terminal connections during installation or risk electric shock, physical injury, or death.
- Loose wiring may cause unit to malfunction, overheat, and catch fire, resulting in severe injury or death.

### Note:

- Terminal screws may loosen during transport. Properly tighten the terminal connections during installation or risk equipment malfunction or property damage.
- Loose wiring may cause unit malfunction, the wires to burnout or the terminal to overheat and catch fire. There is a risk of equipment malfunction or property damage.

A voltage drop may cause the following problems:

- Magnetic switch vibration, fuse breaks, or disturbance to the normal function of an overload protection device.
- Compressor will not receive the proper starting current.

# ELECTRICAL CONNECTIONS

Figure 25: LV180HV4 and LV240HV4 General Power/Communications System Schematic.





Figure 26: LV360HV4, LV480HV, and LV488HV General Power/Communications System Schematic.



## Note:

- Secure the separate wires in the control box panel using zip ties.
- Secure wiring with accessory clamps so that it does not touch the piping.
- Use a conduit for the communications cable / power wiring from the outdoor unit to the indoor units.
- Make sure the communications cable / power wiring from the outdoor units to the indoor units, and the power wiring to the outdoor unit are separate, otherwise, the outdoor unit operation may be affected by electrical noise and will malfunction or fail.

# ELECTRICAL CONNECTIONS

## Connecting the Power Wiring and Communications Cable

1. To access the terminal block, first unscrew the top front panel, and then unscrew the cover from the control box.
2. Knockout the access holes for the wiring. Insert the power wiring/communications cable from the outdoor unit through the conduits, pass the conduits through the designated access holes, and then insert the conduits into the control box. To prevent electro-magnetic interference and product malfunction, leave a space between the power wiring and communications cable outside of the indoor unit.
3. Connect the power wiring and communications cables to the appropriate terminals on the indoor unit control board. Verify that the color and terminal numbers from the outdoor unit wiring match the color and terminal numbers on the indoor unit.
4. Fill in any gaps around the conduit access holes with sealant to prevent foreign particles from entering the indoor unit.

Figure 27: Connecting the Power Wiring and Communications Cable.





Figure 28: Indoor Unit to Outdoor Unit Power Wiring / Communications Cable Connections.



# ELECTRICAL CONNECTIONS

## Controller Options

Vertical Air Handling indoor units include LG-supplied wired controller (PQRCVCL0QW), but other optional LG-supplied wired controllers are available. The wireless handheld controller (Model No. PQWRHQ0FDB) is also an optional accessory with use of the wired controller.

- Operation Display Panel: Displays operation conditions.
- Temperature Control Button: Sets desired temperature.
- Fan Speed Button: Sets desired fan speed.
- On / Off Button: Turns system operation on and off.
- Mode Selection Check Button: Selects the operation mode: Cooling, Heating, Auto, Dry (Dehumidification), or Fan.

### Note:

Each function will display on the LED for about three (3) seconds when the power is first cycled on.

## Wired Controller Connections

Controllers can connect to the indoor unit in one of two different ways.

1. LG Wired Remote Extension Cable with Molex plug (PZCWRC1; sold separately) that connects to the CN-REMO terminal on the indoor unit PCB.
2. Field-supplied controller cable that connects to the indoor unit terminal block (must be at least UL2547 or UL1007, and at least FT-6 rated if local electric and building codes require plenum cable usage). Communication cable from indoor unit to remote controller(s) is to be 22 AWG, 3-conductor, twisted, stranded, unshielded. Wiring must comply with all applicable local and national codes.

Figure 29: PZCWRC1 LG Wired Remote Extension Cable.






Figure 31: Wired Controller Connection on the Indoor Unit Terminal Block.



### Note:

When using field-supplied controller cable, make sure to connect the yellow to yellow (communications wire), red to red (12V power wire), and black to black (ground wire) terminals from the remote controller to the indoor unit terminal blocks.

Figure 30: PQRCVCL0QW Wired Controller.



# ELECTRICAL CONNECTIONS


## Wired Controller Placement

Wired controllers include a sensor to detect room temperature. To maintain comfort levels in the conditioned space, the wired controller must be installed in a location away from direct sunlight, high humidity, and where it could be directly exposed to cold air. Controller must be installed four (4) to five (5) feet above the floor where its LED display can be read easily, in an area with good air circulation, and where it can detect an average room temperature.

⊘ Do not install the wired controller near or in:

- Drafts or dead spots behind doors and in corners
- Hot or cold air from ducts
- Radiant heat from the sun or appliances
- Concealed pipes and chimneys
- An area where temperatures are uncontrolled, such as an outside wall

Figure 32: Proper Location for the Wired Controller.



## Hanging the Wired Controller

1. The controller wiring / cable can be installed in one of three directions: top, back, or on the right side. If top or right side installation is desired, remove cable guide grooves on the controller, and then position wiring / cable on applicable side.
2. Choose and mark the area of installation, and then screw the wall plate into place (using the provided parts). Install the controller wall plate to fit the electrical box if one is present. Ensure that no gaps exist between the wall plate and the wall itself.
3. Arrange wiring / cables so as not to interfere with the controller circuitry. Position the wired controller on the wall plate. Snap into place by pressing the bottom part of the wired controller onto the wall plate. Make sure that no gaps exist between the wired controller and the wall plate on all sides.
4. To remove wired controller from the wall plate, insert a screwdriver into the two holes at the bottom. Twist screwdriver to release controller. ⊘ Do not damage the controller components when removing.

Figure 33: Removing the Cable Guide Grooves.




Figure 34: Attaching the Wall Plate.





Figure 35: Installing / Removing the Controller.




## Assigning the Thermistor for Temperature Detection

Each indoor unit includes a return air thermistor assigned to sense the temperature. If a wired controller is installed, there is a choice of sensing temperature with either the indoor unit return air thermistor or the thermistor in the wired controller. It is also an option to set both thermistors to sense temperature so that indoor unit bases its operation on the first thermistor to reach the designated temperature differential. For applicable indoor units, an optional Remote Temperature Sensor can be used in lieu of the return air thermistor—either alone or in conjunction with a wired controller thermistor as previously described.

# EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES


## External Static Pressure (ESP) Setting Values (NJ frame)

Figure 36: ESP Setting Values (NJ frame).



## External Static Pressure Setting Values (NK frame)

Figure 37: ESP Setting Values (NK frame).





# EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES

## NJ, NK Frames

### IDU External Static Pressure Setting Values

#### LVN180HV4 and LVN240HV4 (NJ Frame)

Table 15: Vertical Air Handling Unit NJ Frame Indoor Unit External Static Pressure and Air Flow Tables.

| Static Pressure (in. wg)                       |                    |     | 0.1                                 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 |
|------------------------------------------------|--------------------|-----|-------------------------------------|-----|-----|-----|-----|-----|-----|
| Model No. / Nominal Capacity of System (Btu/h) | Airflow Rate / CFM |     | Setting Value (in. WG) <sup>1</sup> |     |     |     |     |     |     |
|                                                |                    |     |                                     |     |     |     |     |     |     |
| LVN180HV4/<br>18,000                           | High               | 640 | 63                                  | 67  | 75  | 81  | 88  | 91  | 95  |
|                                                | Mid                | 580 | 57                                  | 63  | 69  | 77  | 84  | 89  | 93  |
|                                                | Low                | 480 | 51                                  | 59  | 65  | 73  | 80  | 87  | 91  |
| LVN240HV4/<br>24,000                           | High               | 710 | 67                                  | 71  | 79  | 85  | 92  | 94  | 97  |
|                                                | Mid                | 640 | 63                                  | 67  | 75  | 81  | 88  | 91  | 95  |
|                                                | Low                | 480 | 51                                  | 59  | 65  | 73  | 80  | 87  | 91  |

### IDU External Static Pressure Setting Values

#### LVN360HV4, LVN420HV, LVN480HV (NK Frame)

Table 16: Vertical Air Handling Unit NK Frame Indoor Unit External Static Pressure and Air Flow Tables.

| Static Pressure (in. wg)                       |                    |       | 0.1                                 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9  | 1    |
|------------------------------------------------|--------------------|-------|-------------------------------------|-----|-----|-----|-----|-----|-----|-----|------|------|
| Model No. / Nominal Capacity of System (Btu/h) | Airflow Rate / CFM |       | Setting Value (in. WG) <sup>1</sup> |     |     |     |     |     |     |     |      |      |
|                                                |                    |       |                                     |     |     |     |     |     |     |     |      |      |
| LVN360HV4/<br>36,000                           | High               | 1,100 | 65                                  | 71  | 79  | 86  | 92  | 96  | 102 | 106 | 112  | —    |
|                                                | Mid                | 1,000 | 61                                  | 67  | 75  | 82  | 88  | 94  | 100 | 104 | 110  | 116* |
|                                                | Low                | 900   | 57                                  | 63  | 71  | 78  | 84  | 92  | 98  | 102 | 108  | 114  |
| LVN420HV/<br>42,000                            | High               | 1,260 | 70                                  | 77  | 83  | 90  | 96  | 98  | 104 | 108 | 116* | —    |
|                                                | Mid                | 1,100 | 65                                  | 71  | 79  | 86  | 92  | 96  | 102 | 106 | 114  | —    |
|                                                | Low                | 1,000 | 61                                  | 67  | 75  | 82  | 88  | 94  | 100 | 104 | 112  | 116* |
| LVN480HV/<br>48,000                            | High               | 1,400 | 77                                  | 82  | 87  | 94  | 100 | 102 | 106 | 110 | 116* | —    |
|                                                | Mid                | 1,260 | 70                                  | 77  | 83  | 90  | 96  | 98  | 104 | 108 | 114  | 116* |
|                                                | Low                | 1,000 | 61                                  | 67  | 75  | 82  | 88  | 94  | 100 | 104 | 112  | 116* |

<sup>1</sup> Unless otherwise noted, vertical air handling units are UL listed up to 0.5 in. wg total static pressure, including coil, case, duct work pressure drop, air filter, and largest kW size heater. Internal static pressure includes coil and case only.

Factory default status is 0.3 in wg.

Factory default is high static pressure.

\* Airflow rate (CFM) decreases by 3% per 0.1 in. wg.

#### Note:

- If the ESP is set incorrectly, the air conditioning may malfunction.
- To get the desired air flow and external static pressure combination, use the setting value from the table. Using a setting value other than the values listed in the table will not provide the desired combination.

# EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES

## Air Filter Static Pressure Drop Factors

Table 17: Air Filter Static Pressure Drop Factors.

| Capacity (kBtu/h [tons]) | Flow Rate (CFM) | Static Pressure Drop (in wg) |
|--------------------------|-----------------|------------------------------|
| 18 (1.5)                 | High (640)      | -0.04                        |
|                          | Middle(580)     | -0.04                        |
|                          | Low (480)       | -0.04                        |
| 24 (2.0)                 | High (710)      | -0.04                        |
|                          | Middle(640)     | -0.04                        |
|                          | Low (480)       | -0.04                        |
| 36 (3.0)                 | High (1100)     | -0.08                        |
|                          | Middle(1000)    | -0.08                        |
|                          | Low (900)       | -0.08                        |
| 42 (3.5)                 | High (1260)     | -0.09                        |
|                          | Middle(1100)    | -0.08                        |
|                          | Low (1000)      | -0.08                        |
| 48 (4.0)                 | High (1400)     | -0.09                        |
|                          | Middle(1260)    | -0.09                        |
|                          | Low (1000)      | -0.08                        |

If the air filter has been installed, the ESP value has to be set.

For every increase in static pressure by 0.01 in. wg, the ESP value should be increased by 1.

## Minimum Airflow by Heater Capacity

Table 18: Minimum Airflow by Heater Capacity.

| Capacity (kBtu/h [tons]) | Heater Capacity (kW) |       |               |               |
|--------------------------|----------------------|-------|---------------|---------------|
|                          | 3, 5                 | 8, 10 | 15            | 20            |
| 18 (1.5)                 | 480                  | 480   | Not available | Not available |
| 24 (2.0)                 | 480                  | 480   | Not available | Not available |
| 36 (3.0)                 | 900                  | 900   | 900           | 900           |
| 42 (3.5)                 | 1000                 | 1000  | 1000          | 1000          |
| 48 (4.0)                 | 1000                 | 1000  | 1000          | 1000          |

Airflow rates in the table above are listed in CFM.

### **⚠ WARNING**

⊘ Do not operate with less than the minimum airflow. If an airflow is used below the minimum, there is a risk of fire, which may lead to physical injury or death.

### **Note:**

⊘ Do not operate with less than the minimum airflow. If an airflow is used below the minimum, there is a risk of damage to the product.

# EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES

## Electric Heater Static Pressure Drop Factors

Table 19: Electric Heater Static Pressure Drop Factors.

| Heater Capacity (kW) | Static Pressure Drop (in. wg) |
|----------------------|-------------------------------|
| 0                    | 0                             |
| 3, 5                 | -0.01                         |
| 8, 10                | -0.02                         |
| 15                   | -0.03                         |
| 20                   | -0.04                         |

in wg = inch water gauge

If the electric heater has been installed, then the ESP value has to be set.

For every increase in static pressure by 0.01 in wg, the ESP value should be increased by 1.

If the ESP setting value is inappropriate, the provided safety device will turn the heater off according to the airflow.

## Down Flow (optional) Static Pressure Drop Factors

Table 20: Down Flow Static Pressure Drop Factors.

| Capacity (kBtu/h [tons]) | Flow Rate (CFM) | Static Pressure Drop (in wg) |
|--------------------------|-----------------|------------------------------|
| 18 (1.5)                 | High (640)      | -0.04                        |
|                          | Middle(580)     | -0.04                        |
|                          | Low (480)       | -0.04                        |
| 24 (2.0)                 | High (710)      | -0.04                        |
|                          | Middle(640)     | -0.04                        |
|                          | Low (480)       | -0.04                        |
| 36 (3.0)                 | High (1100)     | -0.09                        |
|                          | Middle(1000)    | -0.09                        |
|                          | Low (900)       | -0.09                        |
| 42 (3.5)                 | High (1260)     | -0.09                        |
|                          | Middle(1100)    | -0.09                        |
|                          | Low (1000)      | -0.09                        |
| 48 (4.0)                 | High (1400)     | -0.09                        |
|                          | Middle(1260)    | -0.09                        |
|                          | Low (1000)      | -0.09                        |

If the air filter has been installed, the ESP value has to be set.

For every increase in static pressure by 0.01 in. wc, the ESP value should be increased by 1.

# EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES

## Down Flow - Air Filter (optional) Static Pressure Drop Factors

Table 21: Down Flow - Air Filter Static Pressure Drop Factors.

| Capacity (kBtu/h [tons]) | Flow Rate (CFM) | Static Pressure Drop (in wg) |
|--------------------------|-----------------|------------------------------|
| 18 (1.5)                 | High (640)      | -0.04                        |
|                          | Middle(580)     | -0.04                        |
|                          | Low (480)       | -0.04                        |
| 24 (2.0)                 | High (710)      | -0.04                        |
|                          | Middle(640)     | -0.04                        |
|                          | Low (480)       | -0.04                        |
| 36 (3.0)                 | High (1100)     | -0.06                        |
|                          | Middle(1000)    | -0.06                        |
|                          | Low (900)       | -0.06                        |
| 42 (3.5)                 | High (1260)     | -0.07                        |
|                          | Middle(1100)    | -0.06                        |
|                          | Low (1000)      | -0.06                        |
| 48 (4.0)                 | High (1400)     | -0.07                        |
|                          | Middle(1260)    | -0.07                        |
|                          | Low (1000)      | -0.06                        |

If the air filter has been installed, the ESP value has to be set.

For every increase in static pressure by 0.01 in. wc, the ESP value should be increased by 1.

## Down Flow - Internal Electric Heater Static Pressure Drop Factors

Table 22: Internal Electric Heater Static Pressure Drop Factors.

| Heater Capacity (kW) | Static Pressure Drop (in. wg) |
|----------------------|-------------------------------|
| 0                    | 0                             |
| 3, 5                 | -0.01                         |
| 8, 10                | -0.01                         |
| 15                   | -0.01                         |
| 20                   | -0.01                         |

in. wc = inch water column, inAq

If the internal electric heater has been installed, then the ESP value has to be set.

For every increase in static pressure by 0.01 in WC, the ESP value should be increased by 1.

If the ESP setting value is inappropriate, the provided safety device will turn the heater off according to the airflow.

# ACCESSORIES


## Electric Heater

Table 23: Electric Heater Capacities for Vertical Air Handling Units.

| Accessory            | Model Number |
|----------------------|--------------|
| 3kW Electric Heater  | ANEH033B1    |
| 5kW Electric Heater  | ANEH053B1    |
| 8kW Electric Heater  | ANEH083B2    |
| 10kW Electric Heater | ANEH103B2    |
| 15kW Electric Heater | ANEH153B2    |
| 20kW Electric Heater | ANEH203B2    |

Figure 38: Electric Heater.

### Example: 5kW Capacity Heater



**Note:**

Image shown above may vary depending on model capacity.

## Electric Heater, continued

Table 24: Electric Heater Capacities.

| Indoor Unit Model No. / Capacity (MBh) | Model Number / Heater Capacity |                    |                    |                     |                     |                     |
|----------------------------------------|--------------------------------|--------------------|--------------------|---------------------|---------------------|---------------------|
|                                        | ANEH033B1<br>(3kW)             | ANEH053B1<br>(5kW) | ANEH083B2<br>(8kW) | ANEH103B2<br>(10kW) | ANEH153B2<br>(15kW) | ANEH203B2<br>(20kW) |
| LVN180HV4 (18)                         | √                              | √                  | √                  | √                   | X                   | X                   |
| LVN240HV4 (24)                         | √                              | √                  | √                  | √                   | X                   | X                   |
| LVN360HV4 (36)                         | √                              | √                  | √                  | √                   | √                   | √                   |
| LVN420HV (42)                          | √                              | √                  | √                  | √                   | √                   | √                   |
| LVN480HV (48)                          | √                              | √                  | √                  | √                   | √                   | √                   |

√ = Standard feature

X = Not Available

## Base Pan Heater

Figure 39: Base Pan Heater.



Table 25: Base Pan Heater Capacities.

| IDU       | ODU      | Heater kW | Accessory Model | Note     |
|-----------|----------|-----------|-----------------|----------|
| LVN180HV4 | LUU188HV | 120 W     | PQSH1200        | Optional |
| LVN240HV4 | LUU248HV | 120 W     | PQSH1200        | Optional |
| LVN360HV4 | LUU368HV | 120 W     | PQSH1200        | Optional |
| LVN420HV  | LUU428HV | 120 W     | PQSH1200        | Optional |
| LVN480HV  | LUU488HV | 120 W     | PQSH1200        | Optional |

# ACCESSORIES


## LG Monitoring View (LGMV) Diagnostic Software and Cable

LGMV software allows the service technician or commissioning agent to connect a computer USB port to the outdoor unit main printed circuit board (PCB) using an accessory cable without the need for a separate interface device. The main screen for LGMV allows user to view the following real time data on one screen:

- Actual inverter compressor speed
- Target inverter compressor speed
- Actual outdoor fan speed
- Target outdoor unit fan speed
- Actual superheat
- Target superheat
- Actual subcooler circuit superheat
- Target subcooler circuit superheat
- Main EEV position
- Subcooling EEV position
- Inverter compressor current transducer value
- Outdoor air temperature
- Actual high pressure/saturation temperature
- Actual low pressure/saturation temperature
- Suction temperature
- Inverter compressor discharge temperature
- Constant speed compressor discharge temperature
- Front outdoor coil pipe temperature
- Back outdoor coil pipe temperature
- Liquid line pipe temperature
- Subcooler inlet temperature
- Subcooler outlet temperature
- Average indoor unit (IDU) pipe temperature
- Inverter compressor operation indicator light
- Four-way reversing valve operation indicator light
- Pressure graph showing actual low pressure and actual high pressure levels
- Error code display
- Operating mode indicator
- Target high pressure
- Target low pressure
- PCB (printed circuit board) version
- Software version
- Installer name
- Model no. of outdoor units
- Site name
- Total number of connected indoor units
- Communication indicator lights
- Indoor unit capacity
- Indoor unit operating mode
- Indoor unit fan speed
- Indoor unit EEV position
- Indoor unit room temperature
- Indoor unit inlet pipe temperature
- Indoor unit outlet pipe temperature
- Indoor unit error code



Figure 40: Sample Cycleview.



Additional screens can be accessed by tabs on the main screen:

1. Cycleview: Graphic of internal components including:
  - Compressors showing actual speeds
  - EEVs
  - Indoor Units
  - Liquid injection valves
  - Temperature and pressure sensors
  - Four-way reversing valve
  - Outdoor fans showing status and speeds
2. Graph: Full screen graph of actual high and low pressures and high and low pressure limits. A sliding bar enables user to go back in time and view data.
3. Control IDU: Enables user to turn on all IDU's default setpoints of 86°F in heat mode or 64°F in cool mode.
4. Setting: Converts metric values to imperial values.
5. Making Data: Recording of real time data to a separate file created to be stored on the user's computer.
6. Loading Data: Recorded data from a saved ".CSV" file can be loaded to create an LGMV session.
7. Electrical Data: The lower half of main screen is changed to show the following:
  - Inverter compressor
    - Amps
    - Volts
    - Power Hz
    - Inverter control board fan Hz
  - Constant compressor
    - Current transducer value
    - Phase

In lieu of connecting to the outdoor unit, user has the option to connect to the indoor unit with the use of a USB to RS-485 connector kit. When connected through the indoor unit, user will not be able to record data.

This software can be used to both commission new systems and troubleshoot existing systems. LGMV data can be recorded to a ".CSV" file and emailed to an LG representative to assist with diagnostic evaluations.

### Recommended Minimum PC Configuration:

- CPU: Pentium® IV 1.6 GHz
- Operating System: Windows® NT/2000/XP/Vista
- Main Memory: 256 MB
- Hard Disk: 600 MB when operating
- Web Browser: Internet Explorer® 5.0

**LGMV is available in different formats, including Mobile LGMV, which is a app for use on wireless devices. Contact your LG Sales Representative for more information.**

# VERTICAL AIR HANDLING UNIT PERFORMANCE DATA

**“Cooling Capacity Data” on page 52**

**“Heating Capacity Data” on page 57**

**“Maximum Heating Capacity Data” on page 62**

**“Equipment Selection Procedure” on page 67**



# PERFORMANCE DATA

## Cooling Capacity Tables

### Cooling Capacity Table for LV180HV4 (LUU188HV + LVN180HV4)

Table 26: Cooling Capacity Table for LUU188HV + LVN180HV4.

| Outdoor Air Temp. (°F DB) | Indoor Air Temp. °F DB / °F WB |       |      |         |       |      |         |       |      |         |       |      |         |       |      |         |       |      |
|---------------------------|--------------------------------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|
|                           | 68 / 57                        |       |      | 72 / 61 |       |      | 77 / 64 |       |      | 80 / 67 |       |      | 86 / 72 |       |      | 90 / 75 |       |      |
|                           | TC                             | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   |
| -4                        | 17.70                          | 12.85 | 0.80 | 18.80   | 13.58 | 0.83 | 19.89   | 13.14 | 0.86 | 20.69   | 13.42 | 0.87 | 22.09   | 13.53 | 0.88 | 23.19   | 13.79 | 0.90 |
| 0                         | 17.69                          | 12.93 | 0.81 | 18.79   | 13.66 | 0.84 | 19.88   | 13.22 | 0.87 | 20.68   | 13.50 | 0.88 | 22.08   | 13.61 | 0.89 | 23.18   | 13.87 | 0.91 |
| 5                         | 17.67                          | 13.04 | 0.82 | 18.77   | 13.77 | 0.85 | 19.87   | 13.34 | 0.88 | 20.66   | 13.62 | 0.89 | 22.06   | 13.73 | 0.91 | 23.16   | 13.99 | 0.93 |
| 10                        | 17.66                          | 13.14 | 0.83 | 18.76   | 13.88 | 0.86 | 19.85   | 13.44 | 0.89 | 20.64   | 13.73 | 0.90 | 22.05   | 13.84 | 0.92 | 23.14   | 14.10 | 0.94 |
| 15                        | 17.65                          | 13.25 | 0.84 | 18.74   | 13.99 | 0.88 | 19.84   | 13.55 | 0.91 | 20.63   | 13.83 | 0.92 | 22.03   | 13.95 | 0.94 | 23.12   | 14.22 | 0.95 |
| 20                        | 17.63                          | 13.35 | 0.86 | 18.73   | 14.10 | 0.89 | 19.82   | 13.65 | 0.92 | 20.61   | 13.94 | 0.93 | 22.01   | 14.06 | 0.95 | 23.11   | 14.33 | 0.97 |
| 25                        | 17.62                          | 13.45 | 0.87 | 18.71   | 14.21 | 0.90 | 19.81   | 13.76 | 0.93 | 20.60   | 14.05 | 0.94 | 22.00   | 14.17 | 0.96 | 23.09   | 14.44 | 0.98 |
| 30                        | 17.60                          | 13.56 | 0.88 | 18.70   | 14.32 | 0.91 | 19.79   | 13.87 | 0.95 | 20.58   | 14.16 | 0.96 | 21.98   | 14.28 | 0.98 | 23.07   | 14.55 | 1.00 |
| 35                        | 17.59                          | 13.66 | 0.89 | 18.68   | 14.43 | 0.93 | 19.78   | 13.97 | 0.96 | 20.57   | 14.27 | 0.97 | 21.96   | 14.39 | 0.99 | 23.05   | 14.66 | 1.01 |
| 40                        | 17.58                          | 13.76 | 0.91 | 18.67   | 14.54 | 0.94 | 19.76   | 14.08 | 0.97 | 20.55   | 14.37 | 0.98 | 21.94   | 14.49 | 1.00 | 23.04   | 14.77 | 1.02 |
| 45                        | 17.56                          | 13.87 | 0.92 | 18.66   | 14.65 | 0.95 | 19.75   | 14.18 | 0.99 | 20.53   | 14.48 | 1.00 | 21.93   | 14.60 | 1.02 | 23.02   | 14.88 | 1.04 |
| 50                        | 17.55                          | 13.97 | 0.93 | 18.64   | 14.75 | 0.96 | 19.73   | 14.29 | 1.00 | 20.52   | 14.59 | 1.01 | 21.91   | 14.71 | 1.03 | 23.00   | 14.99 | 1.05 |
| 55                        | 17.54                          | 14.07 | 0.94 | 18.63   | 14.86 | 0.98 | 19.72   | 14.39 | 1.01 | 20.50   | 14.69 | 1.02 | 21.89   | 14.82 | 1.04 | 22.98   | 15.10 | 1.06 |
| 60                        | 17.52                          | 14.17 | 0.95 | 18.61   | 14.97 | 0.99 | 19.70   | 14.50 | 1.03 | 20.49   | 14.80 | 1.04 | 21.88   | 14.93 | 1.06 | 22.97   | 15.21 | 1.08 |
| 65                        | 17.51                          | 14.27 | 0.97 | 18.60   | 15.08 | 1.00 | 19.69   | 14.60 | 1.04 | 20.47   | 14.91 | 1.05 | 21.86   | 15.03 | 1.07 | 22.95   | 15.32 | 1.09 |
| 70                        | 17.50                          | 14.38 | 0.98 | 18.58   | 15.19 | 1.01 | 19.67   | 14.70 | 1.05 | 20.46   | 15.01 | 1.06 | 21.84   | 15.14 | 1.08 | 22.93   | 15.43 | 1.10 |
| 75                        | 17.08                          | 14.14 | 1.03 | 18.16   | 14.96 | 1.07 | 19.24   | 14.50 | 1.11 | 20.03   | 14.81 | 1.12 | 21.41   | 14.96 | 1.14 | 22.50   | 15.25 | 1.16 |
| 80                        | 16.66                          | 13.90 | 1.08 | 17.74   | 14.72 | 1.12 | 18.82   | 14.29 | 1.16 | 19.60   | 14.61 | 1.18 | 20.98   | 14.77 | 1.20 | 22.06   | 15.07 | 1.22 |
| 85                        | 16.24                          | 13.64 | 1.14 | 17.32   | 14.47 | 1.18 | 18.40   | 14.06 | 1.22 | 19.17   | 14.39 | 1.24 | 20.55   | 14.57 | 1.26 | 21.63   | 14.88 | 1.28 |
| 90                        | 15.82                          | 13.39 | 1.19 | 16.90   | 14.22 | 1.23 | 17.97   | 13.84 | 1.28 | 18.75   | 14.17 | 1.29 | 20.12   | 14.36 | 1.32 | 21.20   | 14.69 | 1.34 |
| 95                        | 15.37                          | 13.25 | 1.24 | 16.44   | 14.09 | 1.29 | 17.51   | 13.73 | 1.33 | 18.00   | 13.86 | 1.35 | 19.65   | 14.29 | 1.38 | 20.72   | 14.62 | 1.40 |
| 100                       | 14.99                          | 12.89 | 1.30 | 16.06   | 13.74 | 1.34 | 17.13   | 13.40 | 1.39 | 17.77   | 13.65 | 1.41 | 19.28   | 13.98 | 1.43 | 20.35   | 14.32 | 1.46 |
| 105                       | 14.62                          | 12.54 | 1.35 | 15.69   | 13.38 | 1.40 | 16.76   | 13.08 | 1.45 | 17.53   | 13.43 | 1.46 | 18.90   | 13.67 | 1.49 | 19.97   | 14.02 | 1.52 |
| 110                       | 14.24                          | 12.11 | 1.40 | 15.32   | 12.95 | 1.45 | 16.39   | 12.67 | 1.50 | 17.16   | 13.03 | 1.52 | 18.53   | 13.29 | 1.55 | 19.60   | 13.64 | 1.58 |
| 115                       | 13.87                          | 11.75 | 1.45 | 14.94   | 12.58 | 1.51 | 16.01   | 12.34 | 1.56 | 16.79   | 12.70 | 1.58 | 18.15   | 12.97 | 1.61 | 19.22   | 13.33 | 1.64 |
| 118                       | 13.65                          | 11.66 | 1.49 | 14.72   | 12.51 | 1.54 | 15.79   | 12.27 | 1.60 | 16.56   | 12.64 | 1.61 | 17.93   | 12.92 | 1.64 | 19.00   | 13.29 | 1.68 |
| 122                       | 13.57                          | 11.63 | 1.53 | 14.64   | 12.48 | 1.58 | 15.71   | 12.25 | 1.64 | 16.49   | 12.62 | 1.66 | 17.85   | 12.91 | 1.69 | 18.92   | 13.28 | 1.72 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.

3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible. ⓧ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

# PERFORMANCE DATA

## Cooling Capacity Tables

### Cooling Capacity Table for LV240HV4 (LUU248HV + LVN240HV4)

Table 27: Cooling Capacity Table for LUU248HV + LVN240HV4.

| Outdoor Air Temp. (°F DB) | Indoor Air Temp. °F DB / °F WB |       |      |         |       |      |         |       |      |         |       |      |         |       |      |         |       |      |
|---------------------------|--------------------------------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|
|                           | 68 / 57                        |       |      | 72 / 61 |       |      | 77 / 64 |       |      | 80 / 67 |       |      | 86 / 72 |       |      | 90 / 75 |       |      |
|                           | TC                             | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   |
| -4                        | 23.60                          | 17.36 | 1.14 | 25.06   | 18.34 | 1.18 | 26.53   | 17.75 | 1.22 | 27.58   | 18.13 | 1.23 | 29.46   | 18.28 | 1.26 | 30.92   | 18.63 | 1.28 |
| 0                         | 23.58                          | 17.46 | 1.15 | 25.05   | 18.44 | 1.19 | 26.51   | 17.86 | 1.23 | 27.57   | 18.23 | 1.25 | 29.44   | 18.39 | 1.27 | 30.91   | 18.74 | 1.30 |
| 5                         | 23.56                          | 17.61 | 1.17 | 25.03   | 18.60 | 1.21 | 26.49   | 18.01 | 1.25 | 27.55   | 18.39 | 1.27 | 29.42   | 18.55 | 1.29 | 30.88   | 18.90 | 1.32 |
| 10                        | 23.55                          | 17.75 | 1.18 | 25.01   | 18.75 | 1.23 | 26.47   | 18.16 | 1.27 | 27.53   | 18.54 | 1.29 | 29.39   | 18.70 | 1.31 | 30.86   | 19.05 | 1.34 |
| 15                        | 23.53                          | 17.89 | 1.20 | 24.99   | 18.90 | 1.25 | 26.45   | 18.30 | 1.29 | 27.50   | 18.69 | 1.31 | 29.37   | 18.84 | 1.33 | 30.83   | 19.20 | 1.36 |
| 20                        | 23.51                          | 18.03 | 1.22 | 24.97   | 19.05 | 1.26 | 26.43   | 18.44 | 1.31 | 27.48   | 18.83 | 1.32 | 29.35   | 18.99 | 1.35 | 30.81   | 19.35 | 1.38 |
| 25                        | 23.49                          | 18.17 | 1.24 | 24.95   | 19.20 | 1.28 | 26.41   | 18.59 | 1.33 | 27.46   | 18.98 | 1.34 | 29.33   | 19.14 | 1.37 | 30.79   | 19.50 | 1.40 |
| 30                        | 23.47                          | 18.31 | 1.25 | 24.93   | 19.34 | 1.30 | 26.39   | 18.73 | 1.35 | 27.44   | 19.12 | 1.36 | 29.30   | 19.28 | 1.39 | 30.76   | 19.65 | 1.42 |
| 35                        | 23.46                          | 18.45 | 1.27 | 24.91   | 19.49 | 1.32 | 26.37   | 18.87 | 1.37 | 27.42   | 19.27 | 1.38 | 29.28   | 19.43 | 1.41 | 30.74   | 19.80 | 1.43 |
| 40                        | 23.44                          | 18.59 | 1.29 | 24.89   | 19.64 | 1.33 | 26.35   | 19.01 | 1.38 | 27.40   | 19.41 | 1.40 | 29.26   | 19.58 | 1.43 | 30.72   | 19.95 | 1.45 |
| 45                        | 23.42                          | 18.73 | 1.31 | 24.87   | 19.78 | 1.35 | 26.33   | 19.15 | 1.40 | 27.38   | 19.56 | 1.42 | 29.24   | 19.72 | 1.44 | 30.69   | 20.10 | 1.47 |
| 50                        | 23.40                          | 18.87 | 1.32 | 24.85   | 19.93 | 1.37 | 26.31   | 19.30 | 1.42 | 27.36   | 19.70 | 1.44 | 29.21   | 19.87 | 1.46 | 30.67   | 20.24 | 1.49 |
| 55                        | 23.38                          | 19.00 | 1.34 | 24.84   | 20.07 | 1.39 | 26.29   | 19.44 | 1.44 | 27.34   | 19.85 | 1.46 | 29.19   | 20.01 | 1.48 | 30.64   | 20.39 | 1.51 |
| 60                        | 23.37                          | 19.14 | 1.36 | 24.82   | 20.22 | 1.41 | 26.27   | 19.58 | 1.46 | 27.32   | 19.99 | 1.47 | 29.17   | 20.16 | 1.50 | 30.62   | 20.54 | 1.53 |
| 65                        | 23.35                          | 19.28 | 1.37 | 24.80   | 20.37 | 1.42 | 26.25   | 19.72 | 1.48 | 27.29   | 20.13 | 1.49 | 29.15   | 20.30 | 1.52 | 30.60   | 20.69 | 1.55 |
| 70                        | 23.33                          | 19.42 | 1.39 | 24.78   | 20.51 | 1.44 | 26.23   | 19.86 | 1.49 | 27.27   | 20.28 | 1.51 | 29.13   | 20.45 | 1.54 | 30.57   | 20.84 | 1.57 |
| 75                        | 22.77                          | 19.10 | 1.47 | 24.21   | 20.20 | 1.52 | 25.66   | 19.58 | 1.58 | 26.70   | 20.01 | 1.59 | 28.55   | 20.20 | 1.62 | 29.99   | 20.60 | 1.66 |
| 80                        | 22.21                          | 18.77 | 1.54 | 23.65   | 19.88 | 1.60 | 25.09   | 19.30 | 1.66 | 26.13   | 19.73 | 1.68 | 27.97   | 19.95 | 1.71 | 29.42   | 20.36 | 1.74 |
| 85                        | 21.65                          | 18.43 | 1.62 | 23.09   | 19.55 | 1.68 | 24.53   | 18.99 | 1.74 | 25.57   | 19.44 | 1.76 | 27.40   | 19.68 | 1.79 | 28.84   | 20.10 | 1.83 |
| 90                        | 21.09                          | 18.08 | 1.69 | 22.53   | 19.21 | 1.75 | 23.96   | 18.69 | 1.82 | 25.00   | 19.14 | 1.84 | 26.83   | 19.40 | 1.87 | 28.27   | 19.84 | 1.91 |
| 95                        | 20.49                          | 17.89 | 1.77 | 21.92   | 19.03 | 1.83 | 23.35   | 18.55 | 1.90 | 24.00   | 18.72 | 1.92 | 26.20   | 19.30 | 1.96 | 27.63   | 19.75 | 2.00 |
| 100                       | 19.99                          | 17.41 | 1.84 | 21.42   | 18.55 | 1.91 | 22.85   | 18.10 | 1.98 | 23.69   | 18.43 | 2.00 | 25.70   | 18.88 | 2.04 | 27.13   | 19.35 | 2.08 |
| 105                       | 19.49                          | 16.93 | 1.92 | 20.92   | 18.07 | 1.99 | 22.35   | 17.66 | 2.06 | 23.38   | 18.14 | 2.08 | 25.20   | 18.47 | 2.12 | 26.63   | 18.94 | 2.16 |
| 110                       | 18.99                          | 16.35 | 1.99 | 20.42   | 17.49 | 2.06 | 21.85   | 17.12 | 2.14 | 22.88   | 17.60 | 2.16 | 24.70   | 17.94 | 2.21 | 26.13   | 18.42 | 2.25 |
| 115                       | 18.49                          | 15.86 | 2.07 | 19.92   | 17.00 | 2.14 | 21.35   | 16.66 | 2.22 | 22.38   | 17.15 | 2.25 | 24.20   | 17.51 | 2.29 | 25.63   | 18.00 | 2.33 |
| 118                       | 18.19                          | 15.75 | 2.11 | 19.62   | 16.89 | 2.19 | 21.05   | 16.58 | 2.27 | 22.08   | 17.07 | 2.30 | 23.90   | 17.46 | 2.34 | 25.33   | 17.96 | 2.39 |
| 122                       | 18.10                          | 15.71 | 2.17 | 19.52   | 16.86 | 2.25 | 20.95   | 16.55 | 2.33 | 21.98   | 17.05 | 2.36 | 23.81   | 17.44 | 2.40 | 25.23   | 17.94 | 2.45 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.
2. Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.
4. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

# PERFORMANCE DATA

## Cooling Capacity Tables

### Cooling Capacity Table for LV360HV4 (LUU368HV + LVN360HV4)

Table 28: Cooling Capacity Table for LUU368HV + LVN360HV4.

| Outdoor Air Temp. (°F DB) | Indoor Air Temp. °F DB / °F WB |       |      |         |       |      |         |       |      |         |       |      |         |       |      |         |       |      |
|---------------------------|--------------------------------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|
|                           | 68 / 57                        |       |      | 72 / 61 |       |      | 77 / 64 |       |      | 80 / 67 |       |      | 86 / 72 |       |      | 90 / 75 |       |      |
|                           | TC                             | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   |
| -4                        | 35.39                          | 26.37 | 1.70 | 37.59   | 27.86 | 1.77 | 39.79   | 26.97 | 1.83 | 41.38   | 27.54 | 1.85 | 44.19   | 27.77 | 1.89 | 46.38   | 28.30 | 1.92 |
| 0                         | 35.37                          | 26.52 | 1.72 | 37.57   | 28.02 | 1.79 | 39.77   | 27.13 | 1.85 | 41.35   | 27.70 | 1.87 | 44.16   | 27.94 | 1.91 | 46.36   | 28.46 | 1.95 |
| 5                         | 35.34                          | 26.76 | 1.75 | 37.54   | 28.26 | 1.81 | 39.73   | 27.37 | 1.88 | 41.32   | 27.94 | 1.90 | 44.12   | 28.18 | 1.94 | 46.32   | 28.71 | 1.98 |
| 10                        | 35.32                          | 26.97 | 1.78 | 37.51   | 28.49 | 1.84 | 39.70   | 27.58 | 1.91 | 41.29   | 28.16 | 1.93 | 44.09   | 28.40 | 1.97 | 46.28   | 28.94 | 2.01 |
| 15                        | 35.29                          | 27.18 | 1.80 | 37.48   | 28.71 | 1.87 | 39.67   | 27.80 | 1.94 | 41.26   | 28.39 | 1.96 | 44.06   | 28.63 | 2.00 | 46.25   | 29.17 | 2.04 |
| 20                        | 35.26                          | 27.39 | 1.83 | 37.45   | 28.94 | 1.89 | 39.64   | 28.02 | 1.96 | 41.23   | 28.61 | 1.99 | 44.02   | 28.85 | 2.02 | 46.21   | 29.40 | 2.06 |
| 25                        | 35.24                          | 27.61 | 1.85 | 37.43   | 29.16 | 1.92 | 39.61   | 28.24 | 1.99 | 41.19   | 28.83 | 2.01 | 43.99   | 29.07 | 2.05 | 46.18   | 29.62 | 2.09 |
| 30                        | 35.21                          | 27.82 | 1.88 | 37.40   | 29.39 | 1.95 | 39.58   | 28.45 | 2.02 | 41.16   | 29.05 | 2.04 | 43.96   | 29.30 | 2.08 | 46.14   | 29.85 | 2.12 |
| 35                        | 35.18                          | 28.03 | 1.91 | 37.37   | 29.61 | 1.98 | 39.55   | 28.67 | 2.05 | 41.13   | 29.27 | 2.07 | 43.92   | 29.52 | 2.11 | 46.11   | 30.08 | 2.15 |
| 40                        | 35.16                          | 28.24 | 1.93 | 37.34   | 29.83 | 2.00 | 39.52   | 28.88 | 2.08 | 41.10   | 29.49 | 2.10 | 43.89   | 29.74 | 2.14 | 46.07   | 30.30 | 2.18 |
| 45                        | 35.13                          | 28.45 | 1.96 | 37.31   | 30.05 | 2.03 | 39.49   | 29.10 | 2.10 | 41.07   | 29.71 | 2.13 | 43.86   | 29.96 | 2.17 | 46.04   | 30.53 | 2.21 |
| 50                        | 35.10                          | 28.66 | 1.98 | 37.28   | 30.28 | 2.06 | 39.46   | 29.32 | 2.13 | 41.04   | 29.93 | 2.16 | 43.82   | 30.19 | 2.20 | 46.00   | 30.76 | 2.24 |
| 55                        | 35.08                          | 28.87 | 2.01 | 37.25   | 30.50 | 2.08 | 39.43   | 29.53 | 2.16 | 41.01   | 30.15 | 2.18 | 43.79   | 30.41 | 2.22 | 45.97   | 30.98 | 2.27 |
| 60                        | 35.05                          | 29.08 | 2.04 | 37.23   | 30.72 | 2.11 | 39.40   | 29.74 | 2.19 | 40.97   | 30.37 | 2.21 | 43.76   | 30.63 | 2.25 | 45.93   | 31.21 | 2.30 |
| 65                        | 35.02                          | 29.29 | 2.06 | 37.20   | 30.94 | 2.14 | 39.37   | 29.96 | 2.21 | 40.94   | 30.59 | 2.24 | 43.72   | 30.85 | 2.28 | 45.90   | 31.43 | 2.33 |
| 70                        | 34.99                          | 29.50 | 2.09 | 37.17   | 31.16 | 2.16 | 39.34   | 30.17 | 2.24 | 40.91   | 30.81 | 2.27 | 43.69   | 31.07 | 2.31 | 45.86   | 31.66 | 2.36 |
| 75                        | 34.15                          | 29.01 | 2.20 | 36.32   | 30.69 | 2.28 | 38.49   | 29.75 | 2.36 | 40.05   | 30.40 | 2.39 | 42.82   | 30.69 | 2.44 | 44.99   | 31.30 | 2.48 |
| 80                        | 33.31                          | 28.52 | 2.31 | 35.47   | 30.20 | 2.40 | 37.64   | 29.31 | 2.48 | 39.20   | 29.98 | 2.51 | 41.96   | 30.30 | 2.56 | 44.12   | 30.93 | 2.61 |
| 85                        | 32.48                          | 28.00 | 2.42 | 34.63   | 29.70 | 2.51 | 36.79   | 28.86 | 2.61 | 38.35   | 29.53 | 2.64 | 41.10   | 29.89 | 2.68 | 43.26   | 30.54 | 2.74 |
| 90                        | 31.64                          | 27.47 | 2.54 | 33.79   | 29.18 | 2.63 | 35.94   | 28.39 | 2.73 | 37.50   | 29.08 | 2.76 | 40.25   | 29.48 | 2.81 | 42.40   | 30.14 | 2.87 |
| 95                        | 30.74                          | 27.18 | 2.65 | 32.88   | 28.92 | 2.75 | 35.02   | 28.17 | 2.85 | 36.00   | 28.44 | 2.88 | 39.30   | 29.32 | 2.93 | 41.44   | 30.01 | 2.99 |
| 100                       | 29.99                          | 26.45 | 2.76 | 32.13   | 28.19 | 2.86 | 34.27   | 27.50 | 2.97 | 35.53   | 28.00 | 3.00 | 38.55   | 28.69 | 3.06 | 40.69   | 29.39 | 3.12 |
| 105                       | 29.24                          | 25.72 | 2.88 | 31.38   | 27.46 | 2.98 | 33.52   | 26.83 | 3.09 | 35.07   | 27.56 | 3.12 | 37.80   | 28.06 | 3.18 | 39.94   | 28.78 | 3.25 |
| 110                       | 28.49                          | 24.84 | 2.99 | 30.63   | 26.57 | 3.10 | 32.77   | 26.00 | 3.21 | 34.32   | 26.74 | 3.25 | 37.05   | 27.26 | 3.31 | 39.20   | 27.99 | 3.37 |
| 115                       | 27.74                          | 24.10 | 3.10 | 29.88   | 25.82 | 3.21 | 32.02   | 25.31 | 3.33 | 33.57   | 26.05 | 3.37 | 36.31   | 26.61 | 3.43 | 38.45   | 27.35 | 3.50 |
| 118                       | 27.29                          | 23.93 | 3.17 | 29.43   | 25.66 | 3.28 | 31.57   | 25.19 | 3.40 | 33.12   | 25.94 | 3.44 | 35.86   | 26.52 | 3.51 | 38.00   | 27.28 | 3.58 |
| 122                       | 27.14                          | 23.87 | 3.26 | 29.28   | 25.61 | 3.38 | 31.43   | 25.14 | 3.50 | 32.97   | 25.90 | 3.54 | 35.71   | 26.49 | 3.61 | 37.85   | 27.25 | 3.68 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.

3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible. ⓧ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

# PERFORMANCE DATA

## Cooling Capacity Tables

### Cooling Capacity Table for LV420HV (LUU428HV + LVN420HV)

Table 29: Cooling Capacity Table for LUU428HV + LVN420HV.

| Outdoor Air Temp. (°F DB) | Indoor Air Temp. °F DB / °F WB |       |      |         |       |      |         |       |      |         |       |      |         |       |      |         |       |      |
|---------------------------|--------------------------------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|
|                           | 68 / 57                        |       |      | 72 / 61 |       |      | 77 / 64 |       |      | 80 / 67 |       |      | 86 / 72 |       |      | 90 / 75 |       |      |
|                           | TC                             | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   |
| -4                        | 41.29                          | 29.99 | 2.25 | 43.86   | 31.68 | 2.33 | 46.42   | 30.67 | 2.42 | 48.27   | 31.32 | 2.44 | 51.55   | 31.58 | 2.49 | 54.11   | 32.18 | 2.54 |
| 0                         | 41.27                          | 30.16 | 2.27 | 43.83   | 31.86 | 2.36 | 46.40   | 30.85 | 2.44 | 48.25   | 31.50 | 2.47 | 51.52   | 31.77 | 2.52 | 54.08   | 32.37 | 2.57 |
| 5                         | 41.24                          | 30.42 | 2.31 | 43.80   | 32.14 | 2.39 | 46.36   | 31.12 | 2.48 | 48.21   | 31.77 | 2.51 | 51.48   | 32.04 | 2.56 | 54.04   | 32.65 | 2.61 |
| 10                        | 41.20                          | 30.67 | 2.34 | 43.76   | 32.39 | 2.43 | 46.32   | 31.37 | 2.52 | 48.17   | 32.03 | 2.55 | 51.44   | 32.30 | 2.59 | 54.00   | 32.91 | 2.65 |
| 15                        | 41.17                          | 30.91 | 2.38 | 43.73   | 32.65 | 2.46 | 46.29   | 31.61 | 2.55 | 48.13   | 32.28 | 2.58 | 51.40   | 32.55 | 2.63 | 53.96   | 33.17 | 2.69 |
| 20                        | 41.14                          | 31.15 | 2.41 | 43.70   | 32.91 | 2.50 | 46.25   | 31.86 | 2.59 | 48.10   | 32.53 | 2.62 | 51.36   | 32.81 | 2.67 | 53.92   | 33.43 | 2.72 |
| 25                        | 41.11                          | 31.39 | 2.45 | 43.66   | 33.16 | 2.54 | 46.22   | 32.11 | 2.63 | 48.06   | 32.78 | 2.66 | 51.32   | 33.06 | 2.71 | 53.88   | 33.69 | 2.76 |
| 30                        | 41.08                          | 31.63 | 2.48 | 43.63   | 33.41 | 2.57 | 46.18   | 32.35 | 2.66 | 48.02   | 33.04 | 2.70 | 51.28   | 33.31 | 2.75 | 53.83   | 33.95 | 2.80 |
| 35                        | 41.05                          | 31.87 | 2.51 | 43.60   | 33.67 | 2.61 | 46.15   | 32.60 | 2.70 | 47.99   | 33.29 | 2.73 | 51.24   | 33.57 | 2.78 | 53.79   | 34.20 | 2.84 |
| 40                        | 41.02                          | 32.11 | 2.55 | 43.56   | 33.92 | 2.64 | 46.11   | 32.85 | 2.74 | 47.95   | 33.54 | 2.77 | 51.20   | 33.82 | 2.82 | 53.75   | 34.46 | 2.88 |
| 45                        | 40.98                          | 32.35 | 2.58 | 43.53   | 34.18 | 2.68 | 46.07   | 33.09 | 2.78 | 47.91   | 33.79 | 2.81 | 51.17   | 34.07 | 2.86 | 53.71   | 34.72 | 2.92 |
| 50                        | 40.95                          | 32.59 | 2.62 | 43.50   | 34.43 | 2.71 | 46.04   | 33.34 | 2.81 | 47.88   | 34.04 | 2.84 | 51.13   | 34.32 | 2.90 | 53.67   | 34.97 | 2.96 |
| 55                        | 40.92                          | 32.83 | 2.65 | 43.46   | 34.68 | 2.75 | 46.00   | 33.58 | 2.85 | 47.84   | 34.29 | 2.88 | 51.09   | 34.58 | 2.94 | 53.63   | 35.23 | 2.99 |
| 60                        | 40.89                          | 33.07 | 2.69 | 43.43   | 34.93 | 2.78 | 45.97   | 33.82 | 2.89 | 47.80   | 34.54 | 2.92 | 51.05   | 34.83 | 2.97 | 53.59   | 35.49 | 3.03 |
| 65                        | 40.86                          | 33.31 | 2.72 | 43.40   | 35.18 | 2.82 | 45.93   | 34.07 | 2.92 | 47.77   | 34.78 | 2.96 | 51.01   | 35.08 | 3.01 | 53.55   | 35.74 | 3.07 |
| 70                        | 40.83                          | 33.54 | 2.75 | 43.36   | 35.43 | 2.85 | 45.90   | 34.31 | 2.96 | 47.73   | 35.03 | 2.99 | 50.97   | 35.33 | 3.05 | 53.50   | 36.00 | 3.11 |
| 75                        | 39.84                          | 32.99 | 2.90 | 42.37   | 34.90 | 3.01 | 44.90   | 33.83 | 3.12 | 46.73   | 34.57 | 3.15 | 49.96   | 34.90 | 3.21 | 52.49   | 35.59 | 3.28 |
| 80                        | 38.86                          | 32.43 | 3.05 | 41.39   | 34.35 | 3.16 | 43.91   | 33.33 | 3.28 | 45.73   | 34.09 | 3.32 | 48.95   | 34.46 | 3.38 | 51.48   | 35.17 | 3.45 |
| 85                        | 37.89                          | 31.84 | 3.20 | 40.41   | 33.77 | 3.32 | 42.92   | 32.81 | 3.44 | 44.74   | 33.58 | 3.48 | 47.96   | 33.99 | 3.54 | 50.47   | 34.73 | 3.61 |
| 90                        | 36.91                          | 31.23 | 3.35 | 39.43   | 33.18 | 3.47 | 41.94   | 32.28 | 3.60 | 43.75   | 33.07 | 3.64 | 46.96   | 33.52 | 3.71 | 49.47   | 34.27 | 3.78 |
| 95                        | 35.86                          | 30.91 | 3.50 | 38.36   | 32.88 | 3.62 | 40.85   | 32.04 | 3.76 | 42.00   | 32.34 | 3.80 | 45.85   | 33.34 | 3.87 | 48.35   | 34.12 | 3.95 |
| 100                       | 34.98                          | 30.08 | 3.65 | 37.48   | 32.05 | 3.78 | 39.98   | 31.27 | 3.92 | 41.46   | 31.84 | 3.96 | 44.98   | 32.62 | 4.04 | 47.47   | 33.42 | 4.12 |
| 105                       | 34.11                          | 29.25 | 3.79 | 36.61   | 31.22 | 3.93 | 39.11   | 30.51 | 4.08 | 40.91   | 31.34 | 4.12 | 44.10   | 31.90 | 4.20 | 46.60   | 32.72 | 4.28 |
| 110                       | 33.24                          | 28.25 | 3.94 | 35.74   | 30.21 | 4.09 | 38.23   | 29.57 | 4.24 | 40.04   | 30.40 | 4.28 | 43.23   | 31.00 | 4.36 | 45.73   | 31.83 | 4.45 |
| 115                       | 32.37                          | 27.41 | 4.09 | 34.86   | 29.36 | 4.24 | 37.36   | 28.78 | 4.40 | 39.17   | 29.63 | 4.45 | 42.36   | 30.26 | 4.53 | 44.86   | 31.10 | 4.62 |
| 118                       | 31.84                          | 27.21 | 4.18 | 34.34   | 29.18 | 4.33 | 36.84   | 28.64 | 4.49 | 38.64   | 29.50 | 4.54 | 41.83   | 30.16 | 4.63 | 44.33   | 31.02 | 4.72 |
| 122                       | 31.67                          | 27.14 | 4.30 | 34.16   | 29.12 | 4.46 | 36.66   | 28.59 | 4.62 | 38.47   | 29.45 | 4.67 | 41.66   | 30.12 | 4.76 | 44.16   | 30.99 | 4.86 |

- DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)  
 SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)
1. All capacities are net, evaporator fan motor heat is deducted.
  2. Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
  3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.
  4. Direct interpolation is permissible.  Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.  
 0 ft. level difference between outdoor and indoor units.  
 Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

# PERFORMANCE DATA

## Cooling Capacity Tables

### Cooling Capacity Table for LV480HV (LUU488HV + LVN480HV)

Table 30: Cooling Capacity Table for LUU488HV + LVN480HV.

| Outdoor Air Temp. (°F DB) | Indoor Air Temp. °F DB / °F WB |       |      |         |       |      |         |       |      |         |       |      |         |       |      |         |       |      |
|---------------------------|--------------------------------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|---------|-------|------|
|                           | 68 / 57                        |       |      | 72 / 61 |       |      | 77 / 64 |       |      | 80 / 67 |       |      | 86 / 72 |       |      | 90 / 75 |       |      |
|                           | TC                             | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   | TC      | SHC   | PI   |
| -4                        | 47.19                          | 33.83 | 2.84 | 50.12   | 35.73 | 2.94 | 53.05   | 34.60 | 3.05 | 55.17   | 35.33 | 3.09 | 58.91   | 35.62 | 3.14 | 61.84   | 36.30 | 3.21 |
| 0                         | 47.16                          | 34.02 | 2.87 | 50.09   | 35.94 | 2.98 | 53.02   | 34.80 | 3.08 | 55.14   | 35.53 | 3.12 | 58.88   | 35.83 | 3.18 | 61.81   | 36.51 | 3.24 |
| 5                         | 47.13                          | 34.32 | 2.92 | 50.05   | 36.25 | 3.02 | 52.98   | 35.10 | 3.13 | 55.09   | 35.84 | 3.17 | 58.83   | 36.14 | 3.23 | 61.76   | 36.83 | 3.29 |
| 10                        | 47.09                          | 34.59 | 2.96 | 50.01   | 36.54 | 3.07 | 52.94   | 35.38 | 3.18 | 55.05   | 36.13 | 3.22 | 58.79   | 36.43 | 3.28 | 61.71   | 37.12 | 3.34 |
| 15                        | 47.05                          | 34.87 | 3.00 | 49.98   | 36.83 | 3.11 | 52.90   | 35.66 | 3.23 | 55.01   | 36.41 | 3.26 | 58.74   | 36.72 | 3.33 | 61.67   | 37.41 | 3.39 |
| 20                        | 47.02                          | 35.14 | 3.05 | 49.94   | 37.12 | 3.16 | 52.86   | 35.94 | 3.27 | 54.97   | 36.70 | 3.31 | 58.70   | 37.01 | 3.37 | 61.62   | 37.71 | 3.44 |
| 25                        | 46.98                          | 35.41 | 3.09 | 49.90   | 37.41 | 3.20 | 52.82   | 36.22 | 3.32 | 54.93   | 36.98 | 3.36 | 58.65   | 37.29 | 3.42 | 61.57   | 38.00 | 3.49 |
| 30                        | 46.95                          | 35.68 | 3.13 | 49.86   | 37.69 | 3.25 | 52.78   | 36.50 | 3.37 | 54.88   | 37.26 | 3.41 | 58.61   | 37.58 | 3.47 | 61.52   | 38.29 | 3.54 |
| 35                        | 46.91                          | 35.95 | 3.18 | 49.82   | 37.98 | 3.29 | 52.74   | 36.77 | 3.41 | 54.84   | 37.55 | 3.45 | 58.56   | 37.86 | 3.52 | 61.48   | 38.58 | 3.59 |
| 40                        | 46.87                          | 36.22 | 3.22 | 49.79   | 38.26 | 3.34 | 52.70   | 37.05 | 3.46 | 54.80   | 37.83 | 3.50 | 58.52   | 38.15 | 3.56 | 61.43   | 38.87 | 3.64 |
| 45                        | 46.84                          | 36.49 | 3.26 | 49.75   | 38.55 | 3.38 | 52.66   | 37.33 | 3.51 | 54.76   | 38.11 | 3.55 | 58.47   | 38.43 | 3.61 | 61.38   | 39.16 | 3.68 |
| 50                        | 46.80                          | 36.76 | 3.31 | 49.71   | 38.84 | 3.43 | 52.62   | 37.60 | 3.55 | 54.72   | 38.39 | 3.59 | 58.43   | 38.72 | 3.66 | 61.34   | 39.45 | 3.73 |
| 55                        | 46.77                          | 37.03 | 3.35 | 49.67   | 39.12 | 3.47 | 52.58   | 37.88 | 3.60 | 54.67   | 38.68 | 3.64 | 58.38   | 39.00 | 3.71 | 61.29   | 39.74 | 3.78 |
| 60                        | 46.73                          | 37.30 | 3.39 | 49.63   | 39.40 | 3.52 | 52.54   | 38.15 | 3.64 | 54.63   | 38.96 | 3.69 | 58.34   | 39.29 | 3.76 | 61.24   | 40.03 | 3.83 |
| 65                        | 46.70                          | 37.57 | 3.44 | 49.60   | 39.69 | 3.56 | 52.50   | 38.43 | 3.69 | 54.59   | 39.24 | 3.73 | 58.30   | 39.57 | 3.80 | 61.20   | 40.32 | 3.88 |
| 70                        | 46.66                          | 37.84 | 3.48 | 49.56   | 39.97 | 3.61 | 52.46   | 38.70 | 3.74 | 54.55   | 39.52 | 3.78 | 58.25   | 39.85 | 3.85 | 61.15   | 40.60 | 3.93 |
| 75                        | 45.54                          | 37.22 | 3.67 | 48.43   | 39.36 | 3.80 | 51.32   | 38.16 | 3.94 | 53.41   | 38.99 | 3.98 | 57.10   | 39.37 | 4.06 | 59.99   | 40.15 | 4.14 |
| 80                        | 44.41                          | 36.58 | 3.85 | 47.30   | 38.74 | 3.99 | 50.18   | 37.60 | 4.14 | 52.26   | 38.45 | 4.19 | 55.95   | 38.87 | 4.27 | 58.83   | 39.68 | 4.35 |
| 85                        | 43.30                          | 35.91 | 4.04 | 46.18   | 38.09 | 4.19 | 49.05   | 37.01 | 4.34 | 51.13   | 37.88 | 4.39 | 54.81   | 38.35 | 4.47 | 57.68   | 39.17 | 4.56 |
| 90                        | 42.19                          | 35.23 | 4.23 | 45.06   | 37.43 | 4.38 | 47.93   | 36.42 | 4.54 | 50.00   | 37.30 | 4.60 | 53.66   | 37.81 | 4.68 | 56.53   | 38.66 | 4.78 |
| 95                        | 40.98                          | 34.86 | 4.42 | 43.84   | 37.09 | 4.58 | 46.69   | 36.14 | 4.75 | 48.00   | 36.48 | 4.80 | 52.40   | 37.61 | 4.89 | 55.25   | 38.49 | 4.99 |
| 100                       | 39.98                          | 33.93 | 4.60 | 42.84   | 36.15 | 4.77 | 45.69   | 35.28 | 4.95 | 47.38   | 35.91 | 5.00 | 51.40   | 36.80 | 5.10 | 54.26   | 37.70 | 5.20 |
| 105                       | 38.98                          | 33.00 | 4.79 | 41.84   | 35.22 | 4.97 | 44.69   | 34.42 | 5.15 | 46.76   | 35.35 | 5.21 | 50.40   | 35.99 | 5.31 | 53.26   | 36.91 | 5.41 |
| 110                       | 37.99                          | 31.87 | 4.98 | 40.84   | 34.08 | 5.16 | 43.70   | 33.35 | 5.35 | 45.76   | 34.29 | 5.41 | 49.41   | 34.97 | 5.51 | 52.26   | 35.90 | 5.62 |
| 115                       | 36.99                          | 30.91 | 5.17 | 39.84   | 33.12 | 5.36 | 42.70   | 32.47 | 5.55 | 44.76   | 33.42 | 5.62 | 48.41   | 34.13 | 5.72 | 51.26   | 35.08 | 5.84 |
| 118                       | 36.39                          | 30.69 | 5.28 | 39.24   | 32.92 | 5.47 | 42.10   | 32.30 | 5.67 | 44.16   | 33.27 | 5.74 | 47.81   | 34.02 | 5.85 | 50.66   | 34.99 | 5.96 |
| 122                       | 36.19                          | 30.61 | 5.43 | 39.05   | 32.85 | 5.63 | 41.90   | 32.25 | 5.83 | 43.96   | 33.22 | 5.90 | 47.61   | 33.98 | 6.01 | 50.46   | 34.96 | 6.13 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.

3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

# PERFORMANCE DATA

## Heating Capacity Tables

### Heating Capacity Table for LV180HV4 (LUU188HV + LVN180HV4)

Table 31: Heating Capacity Table for LUU188HV + LVN180HV4.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 7.66                   | 1.26 | 7.08  | 1.31 | 7.05  | 1.32 | 6.97  | 1.33 | 6.90  | 1.34 | 6.59  | 1.39 |
| 0                 | -0.4  | 9.23                   | 1.26 | 8.68  | 1.31 | 8.55  | 1.33 | 8.43  | 1.35 | 8.33  | 1.36 | 7.98  | 1.40 |
| 5                 | 4.5   | 11.10                  | 1.27 | 10.58 | 1.32 | 10.33 | 1.35 | 10.16 | 1.36 | 10.03 | 1.38 | 9.62  | 1.42 |
| 10                | 9     | 12.35                  | 1.28 | 11.85 | 1.33 | 11.52 | 1.36 | 11.32 | 1.38 | 11.16 | 1.39 | 10.72 | 1.44 |
| 17                | 15    | 13.73                  | 1.29 | 13.25 | 1.34 | 12.83 | 1.38 | 12.60 | 1.40 | 12.41 | 1.42 | 11.94 | 1.46 |
| 20                | 19    | 14.56                  | 1.30 | 14.10 | 1.34 | 13.63 | 1.39 | 13.37 | 1.41 | 13.17 | 1.43 | 12.67 | 1.47 |
| 25                | 23    | 15.96                  | 1.32 | 15.49 | 1.36 | 14.95 | 1.41 | 14.66 | 1.44 | 14.44 | 1.46 | 13.89 | 1.50 |
| 30                | 28    | 17.37                  | 1.34 | 16.83 | 1.39 | 16.25 | 1.43 | 15.95 | 1.46 | 15.72 | 1.49 | 15.14 | 1.52 |
| 35                | 32    | 18.78                  | 1.37 | 18.18 | 1.41 | 17.56 | 1.45 | 17.24 | 1.48 | 16.99 | 1.51 | 16.38 | 1.55 |
| 40                | 36    | 19.73                  | 1.41 | 19.18 | 1.45 | 18.57 | 1.50 | 18.25 | 1.53 | 17.99 | 1.55 | 17.34 | 1.59 |
| 45                | 41    | 20.93                  | 1.46 | 20.43 | 1.50 | 19.83 | 1.55 | 19.50 | 1.58 | 19.24 | 1.60 | 18.54 | 1.65 |
| 47                | 43    | 21.41                  | 1.48 | 20.93 | 1.52 | 20.33 | 1.57 | 20.00 | 1.60 | 19.73 | 1.62 | 19.02 | 1.67 |
| 50                | 46    | 21.47                  | 1.47 | 21.04 | 1.51 | 20.52 | 1.55 | 20.22 | 1.58 | 19.98 | 1.60 | 19.31 | 1.64 |
| 55                | 51    | 21.58                  | 1.45 | 21.22 | 1.49 | 20.83 | 1.52 | 20.59 | 1.54 | 20.40 | 1.55 | 19.79 | 1.59 |
| 60                | 56    | 21.68                  | 1.44 | 21.40 | 1.46 | 21.14 | 1.49 | 20.95 | 1.50 | 20.81 | 1.51 | 20.28 | 1.53 |
| 63                | 59    | 21.74                  | 1.43 | 21.51 | 1.45 | 21.32 | 1.47 | 21.18 | 1.48 | 21.06 | 1.48 | 20.57 | 1.50 |
| 68                | 64    | 21.81                  | 1.42 | 21.62 | 1.43 | 21.51 | 1.45 | 21.40 | 1.46 | 21.31 | 1.46 | 20.86 | 1.47 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

# PERFORMANCE DATA

## Heating Capacity Tables

### Heating Capacity Table for LV240HV4 (LUU248HV + LVN240HV4)

Table 32: Heating Capacity Table for LUU248HV + LVN240HV4.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 12.73                  | 1.64 | 11.85 | 1.71 | 11.74 | 1.73 | 11.60 | 1.74 | 11.48 | 1.75 | 10.98 | 1.81 |
| 0                 | -0.4  | 14.51                  | 1.67 | 13.68 | 1.73 | 13.45 | 1.76 | 13.26 | 1.77 | 13.10 | 1.79 | 12.55 | 1.85 |
| 5                 | 4.5   | 16.63                  | 1.70 | 15.86 | 1.76 | 15.48 | 1.79 | 15.23 | 1.81 | 15.03 | 1.83 | 14.42 | 1.89 |
| 10                | 9     | 18.05                  | 1.72 | 17.32 | 1.78 | 16.84 | 1.83 | 16.55 | 1.85 | 16.32 | 1.87 | 15.67 | 1.93 |
| 17                | 15    | 19.61                  | 1.76 | 18.93 | 1.81 | 18.33 | 1.87 | 18.00 | 1.90 | 17.73 | 1.92 | 17.05 | 1.98 |
| 20                | 19    | 20.56                  | 1.78 | 19.90 | 1.83 | 19.24 | 1.90 | 18.88 | 1.93 | 18.59 | 1.96 | 17.89 | 2.02 |
| 25                | 23    | 22.14                  | 1.82 | 21.49 | 1.88 | 20.74 | 1.95 | 20.35 | 1.99 | 20.03 | 2.02 | 19.28 | 2.07 |
| 30                | 28    | 23.75                  | 1.88 | 23.01 | 1.94 | 22.22 | 2.00 | 21.81 | 2.04 | 21.49 | 2.08 | 20.70 | 2.13 |
| 35                | 32    | 25.35                  | 1.93 | 24.54 | 2.00 | 23.71 | 2.05 | 23.28 | 2.10 | 22.94 | 2.14 | 22.11 | 2.19 |
| 40                | 36    | 26.64                  | 1.99 | 25.89 | 2.05 | 25.07 | 2.11 | 24.63 | 2.16 | 24.29 | 2.19 | 23.41 | 2.25 |
| 45                | 41    | 28.26                  | 2.06 | 27.58 | 2.12 | 26.77 | 2.19 | 26.32 | 2.23 | 25.97 | 2.26 | 25.02 | 2.33 |
| 47                | 43    | 28.90                  | 2.08 | 28.26 | 2.15 | 27.45 | 2.22 | 27.00 | 2.26 | 26.64 | 2.29 | 25.67 | 2.36 |
| 50                | 46    | 28.99                  | 2.07 | 28.40 | 2.13 | 27.70 | 2.19 | 27.30 | 2.23 | 26.98 | 2.25 | 26.07 | 2.31 |
| 55                | 51    | 29.13                  | 2.05 | 28.65 | 2.10 | 28.12 | 2.15 | 27.79 | 2.17 | 27.54 | 2.19 | 26.72 | 2.24 |
| 60                | 56    | 29.27                  | 2.03 | 28.89 | 2.07 | 28.53 | 2.10 | 28.29 | 2.12 | 28.09 | 2.13 | 27.38 | 2.17 |
| 63                | 59    | 29.35                  | 2.01 | 29.03 | 2.05 | 28.78 | 2.08 | 28.59 | 2.09 | 28.43 | 2.10 | 27.77 | 2.12 |
| 68                | 64    | 29.44                  | 2.00 | 29.18 | 2.03 | 29.04 | 2.05 | 28.89 | 2.06 | 28.77 | 2.06 | 28.17 | 2.08 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⓧ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

# PERFORMANCE DATA

## Heating Capacity Tables

### Heating Capacity Table for LV360HV4 (LUU368HV + LVN360HV4)

Table 33: Heating Capacity Table for LUU368HV + LVN360HV4.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 16.28                  | 2.30 | 15.09 | 2.39 | 15.00 | 2.41 | 14.82 | 2.43 | 14.68 | 2.44 | 14.02 | 2.53 |
| 0                 | -0.4  | 19.29                  | 2.35 | 18.16 | 2.44 | 17.87 | 2.47 | 17.61 | 2.50 | 17.41 | 2.51 | 16.67 | 2.60 |
| 5                 | 4.5   | 22.86                  | 2.41 | 21.80 | 2.50 | 21.28 | 2.55 | 20.93 | 2.58 | 20.66 | 2.60 | 19.82 | 2.69 |
| 10                | 9     | 25.26                  | 2.47 | 24.24 | 2.55 | 23.56 | 2.62 | 23.16 | 2.65 | 22.83 | 2.68 | 21.93 | 2.76 |
| 17                | 15    | 27.89                  | 2.54 | 26.92 | 2.62 | 26.07 | 2.70 | 25.60 | 2.75 | 25.22 | 2.79 | 24.25 | 2.87 |
| 20                | 19    | 29.49                  | 2.59 | 28.55 | 2.67 | 27.59 | 2.76 | 27.08 | 2.82 | 26.67 | 2.86 | 25.66 | 2.94 |
| 25                | 23    | 32.16                  | 2.69 | 31.21 | 2.76 | 30.12 | 2.87 | 29.55 | 2.93 | 29.10 | 2.97 | 28.00 | 3.05 |
| 30                | 28    | 34.86                  | 2.79 | 33.78 | 2.88 | 32.62 | 2.97 | 32.02 | 3.04 | 31.54 | 3.09 | 30.38 | 3.17 |
| 35                | 32    | 37.55                  | 2.89 | 36.36 | 3.00 | 35.12 | 3.07 | 34.49 | 3.15 | 33.98 | 3.20 | 32.76 | 3.28 |
| 40                | 36    | 39.47                  | 2.98 | 38.36 | 3.08 | 37.14 | 3.17 | 36.49 | 3.23 | 35.98 | 3.29 | 34.68 | 3.37 |
| 45                | 41    | 41.86                  | 3.08 | 40.86 | 3.19 | 39.66 | 3.29 | 39.00 | 3.35 | 38.47 | 3.39 | 37.07 | 3.49 |
| 47                | 43    | 42.82                  | 3.13 | 41.86 | 3.23 | 40.66 | 3.33 | 40.00 | 3.39 | 39.47 | 3.44 | 38.03 | 3.54 |
| 50                | 46    | 42.94                  | 3.11 | 42.08 | 3.20 | 41.04 | 3.29 | 40.44 | 3.34 | 39.97 | 3.38 | 38.62 | 3.47 |
| 55                | 51    | 43.15                  | 3.07 | 42.44 | 3.15 | 41.65 | 3.22 | 41.18 | 3.26 | 40.79 | 3.29 | 39.59 | 3.36 |
| 60                | 56    | 43.36                  | 3.04 | 42.80 | 3.10 | 42.27 | 3.16 | 41.91 | 3.18 | 41.62 | 3.20 | 40.56 | 3.25 |
| 63                | 59    | 43.49                  | 3.02 | 43.01 | 3.07 | 42.64 | 3.12 | 42.35 | 3.13 | 42.12 | 3.14 | 41.14 | 3.18 |
| 68                | 64    | 43.61                  | 3.00 | 43.23 | 3.04 | 43.02 | 3.08 | 42.80 | 3.08 | 42.62 | 3.09 | 41.73 | 3.12 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⓧ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).



# PERFORMANCE DATA

## Heating Capacity Tables

### Heating Capacity Table for LV420HV (LUU428HV + LVN420HV)

Table 34: Heating Capacity Table for LUU428HV + LVN420HV.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 20.39                  | 2.80 | 18.93 | 2.91 | 18.79 | 2.95 | 18.57 | 2.97 | 18.38 | 2.98 | 17.57 | 3.09 |
| 0                 | -0.4  | 23.74                  | 2.85 | 22.37 | 2.96 | 22.00 | 3.01 | 21.68 | 3.04 | 21.43 | 3.06 | 20.53 | 3.17 |
| 5                 | 4.5   | 27.73                  | 2.92 | 26.44 | 3.02 | 25.81 | 3.08 | 25.39 | 3.12 | 25.05 | 3.15 | 24.04 | 3.25 |
| 10                | 9     | 30.40                  | 2.97 | 29.17 | 3.08 | 28.36 | 3.15 | 27.87 | 3.20 | 27.48 | 3.23 | 26.40 | 3.33 |
| 17                | 15    | 33.34                  | 3.05 | 32.18 | 3.15 | 31.16 | 3.25 | 30.60 | 3.30 | 30.15 | 3.34 | 28.99 | 3.44 |
| 20                | 19    | 35.12                  | 3.10 | 34.00 | 3.20 | 32.86 | 3.31 | 32.25 | 3.37 | 31.77 | 3.42 | 30.56 | 3.51 |
| 25                | 23    | 38.10                  | 3.20 | 36.97 | 3.29 | 35.69 | 3.41 | 35.01 | 3.48 | 34.47 | 3.54 | 33.17 | 3.63 |
| 30                | 28    | 41.12                  | 3.31 | 39.84 | 3.41 | 38.47 | 3.52 | 37.77 | 3.60 | 37.20 | 3.66 | 35.84 | 3.75 |
| 35                | 32    | 44.13                  | 3.41 | 42.72 | 3.54 | 41.27 | 3.63 | 40.53 | 3.71 | 39.93 | 3.78 | 38.49 | 3.87 |
| 40                | 36    | 46.38                  | 3.51 | 45.07 | 3.64 | 43.64 | 3.74 | 42.88 | 3.82 | 42.28 | 3.88 | 40.74 | 3.98 |
| 45                | 41    | 49.19                  | 3.64 | 48.01 | 3.76 | 46.60 | 3.88 | 45.82 | 3.95 | 45.20 | 4.00 | 43.56 | 4.12 |
| 47                | 43    | 50.31                  | 3.69 | 49.19 | 3.81 | 47.78 | 3.93 | 47.00 | 4.00 | 46.38 | 4.05 | 44.69 | 4.18 |
| 50                | 46    | 50.46                  | 3.67 | 49.44 | 3.77 | 48.22 | 3.88 | 47.52 | 3.94 | 46.96 | 3.99 | 45.37 | 4.10 |
| 55                | 51    | 50.70                  | 3.63 | 49.86 | 3.72 | 48.94 | 3.80 | 48.38 | 3.85 | 47.93 | 3.88 | 46.51 | 3.97 |
| 60                | 56    | 50.95                  | 3.59 | 50.29 | 3.66 | 49.67 | 3.72 | 49.24 | 3.75 | 48.90 | 3.77 | 47.65 | 3.83 |
| 63                | 59    | 51.10                  | 3.56 | 50.54 | 3.62 | 50.10 | 3.68 | 49.76 | 3.69 | 49.49 | 3.71 | 48.34 | 3.75 |
| 68                | 64    | 51.25                  | 3.54 | 50.80 | 3.59 | 50.54 | 3.63 | 50.29 | 3.64 | 50.08 | 3.65 | 49.03 | 3.68 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible.  Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

# PERFORMANCE DATA

## Heating Capacity Tables

### Heating Capacity Table for LV480HV (LUU488HV + LVN480HV)

Table 35: Heating Capacity Table for LUU488HV + LVN480HV.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 25.60                  | 3.39 | 23.81 | 3.53 | 23.61 | 3.57 | 23.32 | 3.59 | 23.08 | 3.61 | 22.07 | 3.74 |
| 0                 | -0.4  | 29.41                  | 3.47 | 27.72 | 3.61 | 27.25 | 3.66 | 26.86 | 3.69 | 26.55 | 3.72 | 25.43 | 3.85 |
| 5                 | 4.5   | 33.94                  | 3.57 | 32.37 | 3.70 | 31.59 | 3.78 | 31.08 | 3.82 | 30.67 | 3.86 | 29.43 | 3.99 |
| 10                | 9     | 36.97                  | 3.67 | 35.48 | 3.79 | 34.49 | 3.89 | 33.90 | 3.94 | 33.42 | 3.98 | 32.11 | 4.11 |
| 17                | 15    | 40.31                  | 3.79 | 38.91 | 3.91 | 37.68 | 4.03 | 37.00 | 4.10 | 36.45 | 4.15 | 35.05 | 4.27 |
| 20                | 19    | 42.33                  | 3.87 | 40.98 | 3.99 | 39.62 | 4.13 | 38.88 | 4.21 | 38.29 | 4.27 | 36.84 | 4.38 |
| 25                | 23    | 45.72                  | 4.02 | 44.37 | 4.14 | 42.83 | 4.29 | 42.02 | 4.38 | 41.37 | 4.45 | 39.81 | 4.57 |
| 30                | 28    | 49.15                  | 4.19 | 47.63 | 4.33 | 45.99 | 4.46 | 45.15 | 4.56 | 44.48 | 4.64 | 42.84 | 4.75 |
| 35                | 32    | 52.58                  | 4.35 | 50.90 | 4.51 | 49.17 | 4.62 | 48.29 | 4.73 | 47.58 | 4.82 | 45.86 | 4.94 |
| 40                | 36    | 55.26                  | 4.48 | 53.70 | 4.64 | 51.99 | 4.77 | 51.09 | 4.87 | 50.37 | 4.95 | 48.55 | 5.08 |
| 45                | 41    | 58.60                  | 4.64 | 57.20 | 4.79 | 55.52 | 4.94 | 54.60 | 5.03 | 53.86 | 5.11 | 51.90 | 5.25 |
| 47                | 43    | 59.94                  | 4.70 | 58.60 | 4.86 | 56.93 | 5.01 | 56.00 | 5.10 | 55.26 | 5.17 | 53.25 | 5.32 |
| 50                | 46    | 60.12                  | 4.67 | 58.91 | 4.81 | 57.45 | 4.95 | 56.62 | 5.03 | 55.95 | 5.09 | 54.06 | 5.22 |
| 55                | 51    | 60.41                  | 4.62 | 59.41 | 4.74 | 58.31 | 4.85 | 57.65 | 4.91 | 57.11 | 4.95 | 55.42 | 5.06 |
| 60                | 56    | 60.71                  | 4.57 | 59.92 | 4.66 | 59.18 | 4.75 | 58.67 | 4.78 | 58.27 | 4.81 | 56.78 | 4.89 |
| 63                | 59    | 60.88                  | 4.54 | 60.22 | 4.62 | 59.70 | 4.69 | 59.29 | 4.71 | 58.96 | 4.73 | 57.59 | 4.79 |
| 68                | 64    | 61.06                  | 4.52 | 60.52 | 4.57 | 60.22 | 4.63 | 59.91 | 4.64 | 59.67 | 4.65 | 58.42 | 4.69 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)  
 PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)  
 1. All capacities are net, evaporator fan motor heat is deducted.  
 2. Direct interpolation is permissible. Ⓣ Do not extrapolate.  
 Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.  
 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

# PERFORMANCE DATA

## Maximum Heating Capacity Tables

### Maximum Heating Capacity Table for LV180HV4 (LUU188HV + LVN180HV4)

Table 36: Maximum Heating Capacity Table for LUU188HV + LVN180HV4.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 17.28                  | 2.43 | 16.26 | 2.52 | 16.00 | 2.56 | 15.78 | 2.58 | 15.60 | 2.60 | 14.94 | 2.69 |
| 0                 | -0.4  | 17.89                  | 2.37 | 16.95 | 2.45 | 16.61 | 2.50 | 16.35 | 2.53 | 16.15 | 2.55 | 15.49 | 2.63 |
| 5                 | 4.5   | 18.60                  | 2.29 | 17.77 | 2.37 | 17.32 | 2.42 | 17.04 | 2.45 | 16.81 | 2.48 | 16.14 | 2.56 |
| 10                | 9     | 19.08                  | 2.22 | 18.32 | 2.30 | 17.80 | 2.35 | 17.50 | 2.39 | 17.25 | 2.41 | 16.57 | 2.49 |
| 17                | 15    | 19.61                  | 2.13 | 18.93 | 2.19 | 18.33 | 2.26 | 18.00 | 2.30 | 17.73 | 2.33 | 17.05 | 2.40 |
| 20                | 19    | 19.93                  | 2.06 | 19.30 | 2.13 | 18.65 | 2.20 | 18.31 | 2.24 | 18.03 | 2.27 | 17.34 | 2.34 |
| 25                | 23    | 20.47                  | 1.97 | 19.87 | 2.03 | 19.18 | 2.10 | 18.81 | 2.14 | 18.52 | 2.18 | 17.83 | 2.24 |
| 30                | 28    | 21.04                  | 1.88 | 20.38 | 1.94 | 19.68 | 2.00 | 19.32 | 2.05 | 19.03 | 2.08 | 18.33 | 2.13 |
| 35                | 32    | 21.59                  | 1.79 | 20.91 | 1.86 | 20.19 | 1.90 | 19.83 | 1.95 | 19.54 | 1.98 | 18.83 | 2.03 |
| 40                | 36    | 22.69                  | 1.84 | 22.06 | 1.91 | 21.35 | 1.96 | 20.98 | 2.00 | 20.69 | 2.04 | 19.94 | 2.09 |
| 45                | 41    | 24.07                  | 1.91 | 23.49 | 1.97 | 22.80 | 2.04 | 22.42 | 2.07 | 22.12 | 2.10 | 21.32 | 2.16 |
| 47                | 43    | 24.62                  | 1.94 | 24.07 | 2.00 | 23.38 | 2.06 | 23.00 | 2.10 | 22.69 | 2.13 | 21.87 | 2.19 |
| 50                | 46    | 24.69                  | 1.92 | 24.19 | 1.98 | 23.60 | 2.04 | 23.25 | 2.07 | 22.98 | 2.09 | 22.20 | 2.15 |
| 55                | 51    | 24.81                  | 1.90 | 24.40 | 1.95 | 23.95 | 2.00 | 23.68 | 2.02 | 23.46 | 2.04 | 22.76 | 2.08 |
| 60                | 56    | 24.93                  | 1.88 | 24.61 | 1.92 | 24.31 | 1.96 | 24.10 | 1.97 | 23.93 | 1.98 | 23.32 | 2.01 |
| 63                | 59    | 25.01                  | 1.87 | 24.73 | 1.90 | 24.52 | 1.93 | 24.35 | 1.94 | 24.22 | 1.95 | 23.65 | 1.97 |
| 68                | 64    | 25.08                  | 1.86 | 24.86 | 1.88 | 24.73 | 1.91 | 24.61 | 1.91 | 24.51 | 1.91 | 23.99 | 1.93 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

# PERFORMANCE DATA

## Maximum Heating Capacity Tables

### Maximum Heating Capacity Table for LV240HV4 (LUU248HV + LVN240HV4)

Table 37: Maximum Heating Capacity Table for LUU248HV + LVN240HV4.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 18.97                  | 3.13 | 17.79 | 3.24 | 17.55 | 3.30 | 17.31 | 3.32 | 17.12 | 3.35 | 16.39 | 3.47 |
| 0                 | -0.4  | 20.27                  | 3.05 | 19.17 | 3.17 | 18.81 | 3.22 | 18.53 | 3.26 | 18.30 | 3.28 | 17.54 | 3.40 |
| 5                 | 4.5   | 21.81                  | 2.96 | 20.82 | 3.07 | 20.30 | 3.14 | 19.97 | 3.18 | 19.70 | 3.21 | 18.91 | 3.31 |
| 10                | 9     | 22.84                  | 2.88 | 21.92 | 2.98 | 21.30 | 3.06 | 20.94 | 3.10 | 20.64 | 3.13 | 19.83 | 3.23 |
| 17                | 15    | 23.97                  | 2.77 | 23.13 | 2.86 | 22.41 | 2.95 | 22.00 | 3.00 | 21.68 | 3.04 | 20.84 | 3.13 |
| 20                | 19    | 24.66                  | 2.70 | 23.87 | 2.78 | 23.07 | 2.88 | 22.64 | 2.93 | 22.30 | 2.98 | 21.45 | 3.06 |
| 25                | 23    | 25.81                  | 2.59 | 25.05 | 2.67 | 24.18 | 2.77 | 23.72 | 2.82 | 23.35 | 2.87 | 22.47 | 2.94 |
| 30                | 28    | 26.99                  | 2.49 | 26.15 | 2.57 | 25.26 | 2.65 | 24.79 | 2.71 | 24.42 | 2.76 | 23.52 | 2.83 |
| 35                | 32    | 28.17                  | 2.39 | 27.27 | 2.48 | 26.34 | 2.54 | 25.87 | 2.60 | 25.49 | 2.65 | 24.57 | 2.71 |
| 40                | 36    | 29.60                  | 2.46 | 28.77 | 2.55 | 27.85 | 2.62 | 27.37 | 2.67 | 26.98 | 2.72 | 26.01 | 2.79 |
| 45                | 41    | 31.40                  | 2.55 | 30.65 | 2.63 | 29.74 | 2.71 | 29.25 | 2.76 | 28.85 | 2.80 | 27.81 | 2.88 |
| 47                | 43    | 32.11                  | 2.58 | 31.40 | 2.67 | 30.50 | 2.75 | 30.00 | 2.80 | 29.60 | 2.84 | 28.52 | 2.92 |
| 50                | 46    | 32.21                  | 2.57 | 31.56 | 2.64 | 30.78 | 2.72 | 30.33 | 2.76 | 29.97 | 2.79 | 28.96 | 2.87 |
| 55                | 51    | 32.36                  | 2.54 | 31.83 | 2.60 | 31.24 | 2.66 | 30.88 | 2.69 | 30.59 | 2.72 | 29.69 | 2.78 |
| 60                | 56    | 32.52                  | 2.51 | 32.10 | 2.56 | 31.70 | 2.61 | 31.43 | 2.63 | 31.22 | 2.64 | 30.42 | 2.68 |
| 63                | 59    | 32.62                  | 2.50 | 32.26 | 2.54 | 31.98 | 2.57 | 31.76 | 2.59 | 31.59 | 2.60 | 30.85 | 2.63 |
| 68                | 64    | 32.71                  | 2.48 | 32.42 | 2.51 | 32.26 | 2.54 | 32.10 | 2.55 | 31.96 | 2.55 | 31.30 | 2.57 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

# PERFORMANCE DATA

## Maximum Heating Capacity Tables

### Maximum Heating Capacity Table for LV360HV4 (LUU368HV + LVN360HV4)

Table 38: Maximum Heating Capacity Table for LUU368HV + LVN360HV4.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 23.77                  | 4.10 | 22.17 | 4.26 | 21.94 | 4.32 | 21.66 | 4.35 | 21.44 | 4.37 | 20.50 | 4.54 |
| 0                 | -0.4  | 26.64                  | 4.11 | 25.14 | 4.27 | 24.70 | 4.34 | 24.34 | 4.38 | 24.05 | 4.41 | 23.05 | 4.57 |
| 5                 | 4.5   | 30.06                  | 4.13 | 28.68 | 4.28 | 27.98 | 4.37 | 27.52 | 4.42 | 27.16 | 4.46 | 26.07 | 4.61 |
| 10                | 9     | 32.35                  | 4.14 | 31.05 | 4.28 | 30.17 | 4.39 | 29.66 | 4.45 | 29.24 | 4.50 | 28.09 | 4.64 |
| 17                | 15    | 34.86                  | 4.16 | 33.65 | 4.29 | 32.59 | 4.43 | 32.00 | 4.50 | 31.53 | 4.56 | 30.32 | 4.69 |
| 20                | 19    | 36.39                  | 4.17 | 35.23 | 4.30 | 34.05 | 4.45 | 33.42 | 4.53 | 32.92 | 4.60 | 31.66 | 4.72 |
| 25                | 23    | 38.95                  | 4.21 | 37.79 | 4.33 | 36.48 | 4.49 | 35.79 | 4.58 | 35.24 | 4.66 | 33.91 | 4.78 |
| 30                | 28    | 41.54                  | 4.26 | 40.25 | 4.40 | 38.87 | 4.53 | 38.16 | 4.63 | 37.59 | 4.71 | 36.20 | 4.83 |
| 35                | 32    | 44.13                  | 4.31 | 42.72 | 4.46 | 41.27 | 4.58 | 40.53 | 4.69 | 39.93 | 4.77 | 38.49 | 4.89 |
| 40                | 36    | 46.38                  | 4.44 | 45.07 | 4.59 | 43.64 | 4.72 | 42.88 | 4.82 | 42.28 | 4.90 | 40.74 | 5.03 |
| 45                | 41    | 49.19                  | 4.59 | 48.01 | 4.75 | 46.60 | 4.89 | 45.82 | 4.98 | 45.20 | 5.06 | 43.56 | 5.20 |
| 47                | 43    | 50.31                  | 4.66 | 49.19 | 4.81 | 47.78 | 4.96 | 47.00 | 5.05 | 46.38 | 5.12 | 44.69 | 5.27 |
| 50                | 46    | 50.46                  | 4.63 | 49.44 | 4.77 | 48.22 | 4.90 | 47.52 | 4.98 | 46.96 | 5.04 | 45.37 | 5.17 |
| 55                | 51    | 50.70                  | 4.58 | 49.86 | 4.69 | 48.94 | 4.80 | 48.38 | 4.86 | 47.93 | 4.90 | 46.51 | 5.01 |
| 60                | 56    | 50.95                  | 4.53 | 50.29 | 4.62 | 49.67 | 4.70 | 49.24 | 4.74 | 48.90 | 4.77 | 47.65 | 4.84 |
| 63                | 59    | 51.10                  | 4.50 | 50.54 | 4.57 | 50.10 | 4.64 | 49.76 | 4.66 | 49.49 | 4.68 | 48.34 | 4.74 |
| 68                | 64    | 51.25                  | 4.47 | 50.80 | 4.53 | 50.54 | 4.58 | 50.29 | 4.59 | 50.08 | 4.60 | 49.03 | 4.64 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. Ⓣ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

# PERFORMANCE DATA

## Maximum Heating Capacity Tables

### Maximum Heating Capacity Table for LV420HV (LUU428HV + LVN420HV)

Table 39: Maximum Heating Capacity Table for LUU428HV + LVN420HV.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 26.74                  | 4.53 | 24.91 | 4.71 | 24.67 | 4.77 | 24.36 | 4.80 | 24.11 | 4.83 | 23.06 | 5.01 |
| 0                 | -0.4  | 30.25                  | 4.55 | 28.54 | 4.72 | 28.04 | 4.80 | 27.64 | 4.84 | 27.31 | 4.88 | 26.16 | 5.05 |
| 5                 | 4.5   | 34.43                  | 4.57 | 32.85 | 4.74 | 32.05 | 4.84 | 31.53 | 4.89 | 31.11 | 4.94 | 29.86 | 5.10 |
| 10                | 9     | 37.23                  | 4.59 | 35.73 | 4.75 | 34.73 | 4.87 | 34.13 | 4.94 | 33.66 | 4.99 | 32.33 | 5.15 |
| 17                | 15    | 40.31                  | 4.62 | 38.91 | 4.77 | 37.68 | 4.92 | 37.00 | 5.00 | 36.45 | 5.07 | 35.05 | 5.21 |
| 20                | 19    | 42.18                  | 4.64 | 40.83 | 4.78 | 39.47 | 4.95 | 38.74 | 5.04 | 38.15 | 5.11 | 36.70 | 5.26 |
| 25                | 23    | 45.31                  | 4.69 | 43.96 | 4.82 | 42.44 | 5.01 | 41.63 | 5.11 | 40.99 | 5.19 | 39.45 | 5.33 |
| 30                | 28    | 48.47                  | 4.76 | 46.97 | 4.91 | 45.36 | 5.06 | 44.53 | 5.18 | 43.86 | 5.26 | 42.25 | 5.40 |
| 35                | 32    | 51.64                  | 4.82 | 49.99 | 4.99 | 48.29 | 5.12 | 47.42 | 5.24 | 46.73 | 5.34 | 45.04 | 5.47 |
| 40                | 36    | 54.27                  | 4.96 | 52.74 | 5.14 | 51.06 | 5.28 | 50.18 | 5.39 | 49.47 | 5.48 | 47.68 | 5.62 |
| 45                | 41    | 57.56                  | 5.14 | 56.18 | 5.31 | 54.53 | 5.48 | 53.62 | 5.58 | 52.90 | 5.66 | 50.98 | 5.82 |
| 47                | 43    | 58.87                  | 5.21 | 57.56 | 5.38 | 55.91 | 5.55 | 55.00 | 5.65 | 54.27 | 5.73 | 52.30 | 5.90 |
| 50                | 46    | 59.05                  | 5.18 | 57.86 | 5.33 | 56.42 | 5.49 | 55.61 | 5.57 | 54.95 | 5.64 | 53.10 | 5.79 |
| 55                | 51    | 59.33                  | 5.12 | 58.35 | 5.25 | 57.27 | 5.37 | 56.62 | 5.43 | 56.09 | 5.48 | 54.43 | 5.60 |
| 60                | 56    | 59.62                  | 5.07 | 58.85 | 5.17 | 58.12 | 5.26 | 57.63 | 5.30 | 57.23 | 5.33 | 55.76 | 5.41 |
| 63                | 59    | 59.80                  | 5.03 | 59.14 | 5.12 | 58.63 | 5.19 | 58.23 | 5.22 | 57.91 | 5.24 | 56.56 | 5.30 |
| 68                | 64    | 59.97                  | 5.00 | 59.44 | 5.07 | 59.15 | 5.13 | 58.84 | 5.14 | 58.60 | 5.15 | 57.38 | 5.19 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)  
 PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)  
 1. All capacities are net, evaporator fan motor heat is deducted.  
 2. Direct interpolation is permissible. Ⓣ Do not extrapolate.  
 Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.  
 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

# PERFORMANCE DATA

## Maximum Heating Capacity Tables

### Maximum Heating Capacity Table for LV480HV (LUU488HV + LVN480HV)

Table 40: Maximum Heating Capacity Table for LUU488HV + LVN480HV.

| Outdoor Air Temp. |       | Indoor Air Temp.: °FDB |      |       |      |       |      |       |      |       |      |       |      |
|-------------------|-------|------------------------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
|                   |       | 61.0                   |      | 64.0  |      | 68.0  |      | 70.0  |      | 72.0  |      | 75.0  |      |
| °F DB             | °F WB | TC                     | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   | TC    | PI   |
| -4                | -4.4  | 28.29                  | 4.96 | 26.33 | 5.16 | 26.10 | 5.23 | 25.77 | 5.26 | 25.51 | 5.29 | 24.39 | 5.49 |
| 0                 | -0.4  | 32.25                  | 4.97 | 30.41 | 5.16 | 29.89 | 5.24 | 29.46 | 5.29 | 29.11 | 5.33 | 27.89 | 5.52 |
| 5                 | 4.5   | 36.96                  | 4.98 | 35.25 | 5.15 | 34.40 | 5.26 | 33.84 | 5.33 | 33.39 | 5.38 | 32.05 | 5.55 |
| 10                | 9     | 40.11                  | 4.98 | 38.50 | 5.15 | 37.42 | 5.28 | 36.77 | 5.36 | 36.26 | 5.42 | 34.83 | 5.59 |
| 17                | 15    | 43.58                  | 4.99 | 42.06 | 5.15 | 40.74 | 5.31 | 40.00 | 5.40 | 39.41 | 5.47 | 37.89 | 5.63 |
| 20                | 19    | 45.68                  | 5.00 | 44.23 | 5.15 | 42.75 | 5.33 | 41.96 | 5.43 | 41.32 | 5.51 | 39.75 | 5.66 |
| 25                | 23    | 49.21                  | 5.02 | 47.75 | 5.17 | 46.09 | 5.37 | 45.22 | 5.47 | 44.52 | 5.56 | 42.84 | 5.71 |
| 30                | 28    | 52.77                  | 5.07 | 51.14 | 5.24 | 49.38 | 5.40 | 48.47 | 5.52 | 47.75 | 5.62 | 45.99 | 5.76 |
| 35                | 32    | 56.33                  | 5.12 | 54.54 | 5.30 | 52.68 | 5.44 | 51.73 | 5.57 | 50.98 | 5.67 | 49.13 | 5.81 |
| 40                | 36    | 59.20                  | 5.27 | 57.54 | 5.45 | 55.70 | 5.61 | 54.74 | 5.73 | 53.97 | 5.82 | 52.01 | 5.97 |
| 45                | 41    | 62.79                  | 5.46 | 61.29 | 5.64 | 59.48 | 5.82 | 58.50 | 5.92 | 57.71 | 6.01 | 55.61 | 6.18 |
| 47                | 43    | 64.23                  | 5.53 | 62.79 | 5.72 | 61.00 | 5.90 | 60.00 | 6.20 | 59.20 | 6.08 | 57.05 | 6.26 |
| 50                | 46    | 64.41                  | 5.50 | 63.12 | 5.66 | 61.55 | 5.83 | 60.66 | 5.91 | 59.95 | 5.98 | 57.92 | 6.15 |
| 55                | 51    | 64.73                  | 5.44 | 63.66 | 5.57 | 62.48 | 5.71 | 61.76 | 5.77 | 61.19 | 5.82 | 59.38 | 5.95 |
| 60                | 56    | 65.04                  | 5.38 | 64.20 | 5.49 | 63.41 | 5.59 | 62.86 | 5.63 | 62.43 | 5.66 | 60.83 | 5.75 |
| 63                | 59    | 65.23                  | 5.35 | 64.52 | 5.43 | 63.96 | 5.51 | 63.53 | 5.54 | 63.18 | 5.56 | 61.71 | 5.63 |
| 68                | 64    | 65.42                  | 5.31 | 64.85 | 5.38 | 64.52 | 5.44 | 64.19 | 5.46 | 63.93 | 5.47 | 62.59 | 5.51 |

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⓧ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

# EQUIPMENT SELECTION PROCEDURE

## Correction Factors

### Cooling / Heating Correction Factors

For Single Zone Vertical Air Handling Unit systems, calculate the equivalent length of the liquid line from the outdoor unit to the indoor unit. Also, determine the elevation difference of the indoor unit above or below the outdoor unit. Find corresponding cooling or heating capacity correction factors as shown below. Multiply the correction factors by the cooling or heating capacity obtained from the capacity table using design conditions. The result is the NET cooling or heating capacity.

### Refrigerant Line Length Derates

For air-cooled systems, a capacity correction factor may have to be applied to account for the length of the system's refrigerant pipe. Rate of change in capacity due to increased piping lengths is shown below.

### Cooling Capacity Coefficient Factors

Table 41: Vertical Air Handling Unit Cooling Capacity Coefficient Factors.

| Piping Length (ft.)         |                         | 24.6 | 32.8 | 49.2 | 65.6 | 98.4 | 131.2 | 164  | 196.9 | 229.7 | 246  |
|-----------------------------|-------------------------|------|------|------|------|------|-------|------|-------|-------|------|
| Rate of Capacity Change (%) | LUU188HV (18,000 Btu/h) | 100  | 99.3 | 97.9 | 96.6 | 93.8 | 91.1  | 88.4 | -     | -     | -    |
|                             | LUU248HV (24,000 Btu/h) | 100  | 99.3 | 97.9 | 96.6 | 93.8 | 91.1  | 88.4 | -     | -     | -    |
|                             | LUU368HV (36,000 Btu/h) | 100  | 99.3 | 97.9 | 96.6 | 93.8 | 91.1  | 88.4 | 85.6  | 82.9  | 81.5 |
|                             | LUU428HV (42,000 Btu/h) | 100  | 99.3 | 97.9 | 96.6 | 93.8 | 91.1  | 88.4 | 85.6  | 82.9  | 81.5 |
|                             | LUU488HV (48,000 Btu/h) | 100  | 99.3 | 97.9 | 96.6 | 93.8 | 91.1  | 88.4 | 85.6  | 82.9  | 81.5 |

### Heating Capacity Coefficient Factors

Table 42: Vertical Air Handling Unit Heating Capacity Coefficient Factors.

| Piping Length (ft.)         |                         | 24.6 | 32.8 | 49.2 | 65.6 | 98.4 | 131.2 | 164  | 196.9 | 229.7 | 246  |
|-----------------------------|-------------------------|------|------|------|------|------|-------|------|-------|-------|------|
| Rate of Capacity Change (%) | LUU188HV (18,000 Btu/h) | 100  | 99.3 | 97.9 | 96.6 | 91.8 | 91.1  | 88.4 | -     | -     | -    |
|                             | LUU248HV (24,000 Btu/h) | 100  | 99.3 | 97.9 | 96.6 | 91.8 | 91.1  | 88.4 | -     | -     | -    |
|                             | LUU368HV (36,000 Btu/h) | 100  | 99.7 | 99.2 | 98.7 | 97.7 | 96.6  | 95.6 | 94.6  | 93.5  | 93.0 |
|                             | LUU428HV (42,000 Btu/h) | 100  | 99.7 | 99.2 | 98.7 | 97.7 | 96.6  | 95.6 | 94.6  | 93.5  | 93.0 |
|                             | LUU488HV (48,000 Btu/h) | 100  | 99.7 | 99.2 | 98.7 | 97.7 | 96.6  | 95.6 | 94.6  | 93.5  | 93.0 |



# EQUIPMENT SELECTION PROCEDURE

## Correction Factors

### Equivalent Piping Length for Piping Components

Table 43: Equivalent Piping Length for Elbows.

| Component   | Size (Inches) |     |     |     |     |     |     |       |       |       |       |       |       |       |
|-------------|---------------|-----|-----|-----|-----|-----|-----|-------|-------|-------|-------|-------|-------|-------|
| Elbow (ft.) | 1/4           | 3/8 | 1/2 | 5/8 | 3/4 | 7/8 | 1   | 1-1/8 | 1-1/4 | 1-3/8 | 1-1/2 | 1-5/8 | 1-3/4 | 2-1/8 |
|             | 0.5           | 0.6 | 0.7 | 0.8 | 1.2 | 1.3 | 1.5 | 1.6   | 1.8   | 2.0   | 2.1   | 2.3   | 2.5   | 2.8   |

### Altitude Correction Factor

The impact of air density must be considered on systems installed at a significant altitude above sea level, therefore, locally accepted altitude correction factors must be applied.

### Defrost Correction Factor for Heating Operation

The outdoor unit heating capacity may need to be adjusted for frost accumulation on air-cooled systems. If design day conditions are below the dewpoint of the surrounding air, frost may not be a problem and no correction factor is needed. In certain weather conditions, however, frost may form and accumulate on the air-cooled outdoor unit coil and impact the coils ability to transfer heat. If significant frost accumulates on the outdoor unit coil, a defrost algorithm will start automatically. The timing between defrost periods is determined by the system's ability to achieve a target head pressure value.

Capacity and AHRI ratings tables do not factor in capacity reduction when frost has accumulated on the condenser coil, nor during defrost operation.

Integrated heating capacity values can be obtained using the formula: Table 44: Outdoor Unit Frost Accumulation Factor (Heating)<sup>1</sup>.

$$A = B \times C$$

Where:

A = Integrated Heating Capacity.

B = Value found in the Capacity Table.

C = Correction Factor for Frost Accumulation Factor (from table at right).

| Entering DB (°F) | 19.4 | 23.0 | 26.6 | 32.0 | 37.4 | 41.0 | 44.6 |
|------------------|------|------|------|------|------|------|------|
| Derate factor    | 0.98 | 0.95 | 0.93 | 0.86 | 0.93 | 0.96 | 1.0  |

<sup>1</sup>At 85% outdoor air relative humidity.

The frost accumulation factor does not account for effects of snow accumulation restricting airflow through the outdoor unit coil.

### Note:

There will be a temporary reduction in capacity when frost / ice accumulates on the outside surface of the outdoor unit heat exchanger. The level of capacity reduction depends on a number of factors, for example, outdoor temperature (°F DB), relative humidity (RH), and the amount of frost present.

# EQUIPMENT SELECTION PROCEDURE

## Check the Indoor and Outdoor Unit Selection(s)

Compare the corrected cooling and heating capacities to the load calculations. Is each capacity sufficient for the zone it serves?

For each indoor unit, the corrected capacity must be at least equal to the total of the cooling design load (plus ventilation load, if applicable) for the space served by the indoor unit. For each indoor unit, the corrected capacity also must be at least equal to the total of the heating design load (plus ventilation load, if applicable) for the space(s) and / or thermal zones served by the indoor unit.

The outdoor unit selected should be large enough to offset the total cooling load for all spaces it serves (account for ventilation air cooling load if the ventilation air has not been pretreated to room neutral conditions). The outdoor unit should also be large enough to offset the total heating load for all spaces it serves.

If the corrected heating capacity ratio exceeds 100%, reselect the equipment, or change the system design by moving some of the load to another system.

## System Sizing Check Formulas

### 1. Outdoor Unit Rated Capacity.

$Q_{odu(rated)}$  (From capacity tables).

### 2. Outdoor Unit Capacity at $T_i$ , $T_o$ Temperature.

$Q_{odu(T_i, T_o)}$  (From capacity tables).

### 3 Outdoor Unit Capacity Coefficient Factor.

$$F_{(T_i, T_o)} = Q_{odu(T_i, T_o)} / Q_{odu(rated)}$$

### 4. Piping Correction Factor (From Capacity Coefficient Factor Tables).

$F_{(length)}$  for each piping length

### 5. Individual Indoor Unit Combination Capacity.

$$Q_{idu (combi)} = Q_{odu(rated)} \times Q_{idu(rated)} / Q_{idu(rated-total)}$$

### 6. Individual Indoor Unit Actual Capacity.

$$Q_{idu (actual)} = Q_{odu(combi)} \times F_{(T_i, T_o)} \times F_{(length, altitude)}$$

## Conclusions and Recommendations

- Understand the design safety factors.
- Reference load calculations for actual cooling and heating capacities (applies in 99% of applications – consider total load when latent load is greater than 30%).
- Verify that the sensible load of the zone is satisfied.
- Use caution when sizing to meet listed capacity specifications for the scheduled manufacturer's equipment.

If further system design assistance is needed, or you have a unique application you would like to discuss, contact your LG sales rep.

# VERTICAL AIR HANDLING UNIT APPLICATION GUIDELINES

**“Placement Considerations” on page 71**

**“Clearances” on page 75**

**“Installing Outdoor Units Indoors” on page 78**

**“Refrigerant Piping Design” on page 80**

# PLACEMENT CONSIDERATIONS

## Indoor Unit

### Selecting the Best Location for the Indoor Unit

#### Dos

- Place the unit where air circulation will not be blocked.
- Place the unit where drainage can be obtained easily and to minimize the length of the condensate drain piping.
- Place the unit where noise prevention is taken into consideration.
- Place the unit in a location that can support the indoor unit weight, and where the indoor unit can be level.
- The mounting floor must be strong and solid enough to prevent the indoor unit from vibrating.
- Ensure there is sufficient maintenance and clearance space (wall, ceiling, or other obstacles; see diagram for clearances).
- Locate the indoor unit in a location where it can be easily connected to the outdoor unit.



#### Don'ts

- Avoid installing the unit near high-frequency generators.
- No obstacles must be present to prevent indoor unit air circulation.
- Do not install the unit near a doorway.
- Do not install the unit near a heat or steam source, or where considerable amounts of oil, iron powder, or flour are used. (These materials may generate condensate, cause a reduction in heat exchanger efficiency, or the drain pump to malfunction. If this is a potential problem, install a ventilation fan large enough to vent out these materials.)

### WARNING

The unit should not be installed where sulfuric acid and flammable or corrosive gases are generated, vented into, or stored. There is risk of fire, explosion, and physical injury or death.

The unit may be damaged, may malfunction, and / or will not operate as designed if installed in any of the conditions listed.

### Note:

Indoor units (IDUs) should not be placed in an environment where the IDUs may be exposed to harmful volatile organic compounds (VOCs) or in environments where there is improper air make up or supply or inadequate ventilation. If there are concerns about VOCs in the environment where the IDUs are installed, proper air make up or supply and/ or adequate ventilation should be provided. Additionally, in buildings where IDUs will be exposed to VOCs, consider a factory-applied epoxy coating to the fan coils for each IDU.

If the unit is installed near a body of water, the installation parts are at risk of corroding. Appropriate anti-corrosion methods should be taken for the unit and all installation parts.

### Installing in an Area Exposed to Unconditioned Air

In some installation applications, areas (floors, walls) in some rooms may be exposed to unconditioned air (room may be above or next to an unheated garage or storeroom). To countermeasure:

- Verify that carpet is or will be installed (carpet may increase the temperature by three [3] degrees).
- Add insulation between the floor joists.
- Install radiant heat or another type of heating system to the floor.

Figure 41: Recommended Clearances for Vertical Air Handling Unit IDU.





Figure 42: Installing Near a Heat or Steam Source.



# PLACEMENT CONSIDERATIONS

## Outdoor Unit

### Selecting the Best Location for the Outdoor Unit

#### **⚠ DANGER**

- ⊘ Do not install the unit in an area where combustible gas may generate, flow, stagnate, or leak. These conditions can cause a fire, resulting in bodily injury or death.
- ⊘ Do not install the unit in a location where acidic solution and spray (sulfur) are often used as it can cause bodily injury or death.
- ⊘ Do not use the unit in environments where oil, steam, or sulfuric gas are present as it can cause bodily injury or death.

#### **⚠ WARNING**

When deciding on a location to place the outdoor unit, be sure to choose an area where run-off from defrost will not accumulate and freeze on sidewalks or driveways, which may create unsafe conditions. Properly install and insulate any drain hoses to prevent the hose from freezing, cracking, leaking, and causing unsafe conditions from frozen condensate.

Install a fence to prevent vermin from crawling into the unit or unauthorized individuals from accessing it. Follow the placement guidelines set forth in "Clearance Requirements".

Select a location for installing the outdoor unit that will meet the following conditions:

- Where there is enough strength to bear the weight of the outdoor unit.
- A location that allows for optimum air flow and is easily accessible for inspection, maintenance, and service.
- Where piping between the outdoor unit and indoor unit(s) are within allowable limits.
- Include space for drainage to ensure condensate flows properly out of the unit when it is in heating mode. Avoid placing the outdoor unit in a low-lying area where water could accumulate.
- If the outdoor unit is installed in a highly humid environment (near an ocean, lake, etc.), ensure that the site is well-ventilated and has a lot of natural light (Example: Install on a rooftop).



#### **Don'ts**

- Where it will be subjected to direct thermal radiation from other heat sources, or an area that would expose the outdoor unit to heat or steam like discharge from boiler stacks, chimneys, steam relief ports, other air conditioning units, kitchen vents, plumbing vents, and other sources of extreme temperatures.
- Where high-frequency electrical noise / electromagnetic waves will not affect operation.
- Where operating sound from the unit will disturb inhabitants of surrounding buildings.
- Where the unit will be exposed to direct, strong winds.
- Where the discharge of one outdoor unit will blow into the inlet side of an adjacent unit (when installing multiple outdoor units).

### **Note:**

The indoor unit may take longer to provide heat, or heating performance will be reduced in winter if the unit is installed:

1. In a narrow, shady location.
2. Near a location that has a lot of ground moisture.
3. In a highly humid environment.
4. In an area in which condensate does not drain properly.

# PLACEMENT CONSIDERATIONS

## Outdoor Unit

### Planning for Snow and Ice

To ensure the outdoor unit operates properly, certain measures are required in locations where there is a possibility of heavy snowfall or severe windchill or cold:

1. Prepare for severe winter wind chills and heavy snowfall, even in areas of the country where these are unusual phenomena.
2. Position the outdoor unit so that its airflow fans are not buried by direct, heavy snowfall. If snow piles up and blocks the airflow, the system may malfunction.
3. Remove any snow that has accumulated four (4) inches or more on the top of the outdoor unit.
4. In climates that may experience significant snow buildup, mount the outdoor unit on a raised, field-provided platform or stand. The raised support platform must be high enough to allow the unit to remain above possible snow drifts, and must be higher than the maximum anticipated snowfall for the location.
5. Design the mounting base to prevent snow accumulation on the platform in front or back of the unit frame.
6. Provide a field fabricated snow protection hood to keep snow and ice and/or drifting snow from accumulating on the coil surfaces.
7. Install a hail guard kit and air guide accessories (sold separately) to prevent snow or rain from accumulating on the fan inlet / outlet guards.
8. Consider tie-down requirements in case of high winds or where required by local codes.

### ⚠ CAUTION

When deciding on a location to place the outdoor unit, be sure to choose an area where run-off from defrost will not accumulate and freeze on sidewalks or driveways, which may create unsafe conditions.

### Note:

Choose an area where run-off from defrost mode will not accumulate and freeze on sidewalks or driveways. Properly install and insulate any drain hoses to prevent the hose from freezing, cracking, leaking, and damaging the outdoor unit.

## Tie-Downs, Wind Restraints, and Lightning Protection

### Tie-Downs

- The strength of the roof must be checked before installing the outdoor units.
- If the installation site is prone to high winds or earthquakes, when installing on the wall or roof, securely anchor the mounting base using a field-provided tie-down configuration approved by a local professional engineer.
- The overall tie-down configuration must be approved by a local professional engineer. Always refer to local code when using a wind restraint system.

### Note:

Always refer to local code when designing a wind restraint system.

### Lightning Protection


- To protect the outdoor unit from lightning, place the unit within the specified lightning safety zone.

Table 45: Safety Zone Specifications.

| Building Height (feet) | 66 | 98 | 148 | 197 |
|------------------------|----|----|-----|-----|
| Protection Angle (°)   | 55 | 45 | 35  | 25  |

- Power cable and communication cable should be installed five (5) feet away from lightning rod.
- A high-resistance ground system should be included to protect against induced lightning or indirect strike.

Figure 43: Lightning Protection Diagram.



### Note:

If the building does not include lightning protection, the outdoor unit may be damaged from a lightning strike. Inform the customer of this possibility in advance.

# PLACEMENT CONSIDERATIONS

## Outdoor Unit

### Wind Protection

If the outdoor unit is placed on a roof, position it with the compressor end (no coil surface) in the direction of the prevailing wind as shown in the figure at right. In cooler climates, it may be beneficial to position the unit in direct sunlight to assist with defrost operations.

If the outdoor unit is not placed on a roof, place it on the leeward side of the building or in a location where the unit will not be exposed to constant wind.

If placement exposes the unit to constant wind activity, construct a wind break in front of the unit. Follow the placement guidelines set forth in "Clearance Requirements".

Figure 44: Prevailing Wind Direction.





Figure 45: Leeward Side of the Building.



Figure 46: Wind Break.



### Tie-Downs and Wind Restraints

The strength of the Vertical Air Handling Unit frames is adequate to be used with field-provided wind restraint tie-downs. The overall tie-down configuration must be approved by a local professional engineer. Always refer to local code when designing a wind restraint system.

### Mounting Platform

The underlying structure or foundation must be designed to support the weight of the unit. Avoid placing the unit in a low lying area where water may accumulate.

### Oceanside Installation Precautions


#### Note:

*Ocean winds may cause corrosion, particularly on the condenser and evaporator fins, which, in turn could cause product malfunction or inefficient performance.*

- Avoid installing the outdoor unit where it would be directly exposed to ocean winds.
- Install the outdoor unit on the side of the building opposite from direct ocean winds.
- Select a location with good drainage.
- Periodically clean dust or salt particles off of the heat exchanger with water.


If the outdoor unit must be placed in a location where it would be subjected to direct ocean winds, install a concrete windbreaker strong enough to block any winds. Windbreaker height and width should be more than 150% of the outdoor unit, and be installed at least 27-1/2 inches away from the outdoor unit to allow for airflow.

Figure 47: Oceanside Placement Using a Building as Shield, and Placement Using a Windbreaker.



#### Note:

*Additional anti-corrosion treatment may need to be applied to the outdoor unit at oceanside locations.*





### Minimum Clearance Requirements for Vertical Air Handling Unit ODUs

Proper clearance for the outdoor unit coil is critical for proper unit operation. When installing the outdoor unit, consider service, inlet and outlet and minimum allowable space requirements as illustrated in the diagrams below and on the next few pages.

#### Minimum Clearance Requirements for LUU188HV, LUU248HV Outdoor Units

Specific clearance requirements in the diagram below are for 18,000 Btu/h (LUU188HV), and 24,000 Btu/h (LUU248HV) systems. The following figure shows the overall minimum clearances that must be observed for safe operation and adequate airflow around the outdoor unit. When placing the outdoor unit under an overhang, awning, sunroof or other "roof-like structure", observe the clearance requirements (as shown in Cases 1 and 2 for height in relation to the unit. This clearance ensures that heat radiation from the condenser is not restricted around the unit.


Adhere to all clearance requirements if installing the unit on a roof. Be sure to level the unit and ensure that the unit is adequately anchored. Consult local codes for rooftop mounting requirements.

To have successful service access to the outdoor unit, see the following figure for minimum spacing. When installing multiple outdoor units, see Cases 4 and 5 for correct spacing requirements.

#### Note:

If the outdoor unit is installed between standard and minimum clearances, capacity decreases approximately 10%.

Figure 48: Outdoor Unit Service Access and Allowable Clearances Diagram.



#### Note:

Do not place the unit where animals and/or plants will be in the path of the warm air, or where the warm air and / or noise will disturb neighbors.

Table 46: 24K Outdoor Unit Service Access and Allowable Clearances Diagram Legend.

| Unit: Inch |          | A  | B  | C  | D  | E  | F  | G  |
|------------|----------|----|----|----|----|----|----|----|
| Case 1     | Standard | 12 | 24 | -  | 12 | -  | -  | -  |
|            | Minimum  | 4  | 10 | -  | 4  | -  | -  | 40 |
| Case 2     | Standard | -  | -  | 20 | -  | -  | -  | -  |
|            | Minimum  | -  | -  | 14 | -  | -  | -  | 40 |
| Case 3     | Standard | -  | -  | 20 | 12 | -  | -  | -  |
|            | Minimum  | -  | -  | 14 | 4  | -  | -  | -  |
| Case 4     | Standard | -  | -  | -  | 12 | 24 | -  | -  |
|            | Minimum  | -  | -  | -  | 4  | 8  | 79 | -  |
| Case 5     | Standard | -  | 24 | -  | 12 | -  | -  | -  |
|            | Minimum  | -  | 10 | -  | 4  | -  | -  | -  |



# CLEARANCES

## Outdoor Unit

### Minimum Clearance Requirements for LUU368HV, LUU428HV, LUU488HV Outdoor Units

Figures below and on the next page illustrate clearance requirements for various installation scenarios for 38,000 Btu/h (LUU368HV), 42,000 Btu/h (LUU428HV), and 48,000 Btu/h (LUU488HV) outdoor units. Use the hot isle / cold isle approach when placing multiple units in close proximity to each other. Outdoor unit fans draw air from the back of the unit and discharges out the front. Place units back to back and face to face.

#### Note:

- Installation clearances must comply with local building codes.
- All figures not to scale.
-  Never place multiple units facing back to front or front to back as shown immediately below here or high and low system pressure problems may occur.

#### Legend

LR = Rear wall height

LF = Front wall height

H = Unit height

Figure 49: Improper Outdoor Unit Placement.





Figure 50: Proper Outdoor Unit Placement and Clearances.

Single Unit—High Front Wall with Building Overhang and No Side Walls



Single Unit—High Rear Wall and Low Front Wall with No Side Walls






Figure 51: Proper Outdoor Unit Placement and Clearances, continued.


Single Unit—High Rear Wall with or without High Side Walls




Single Unit—High Rear and Front Walls with No Side Walls




Side by Side—High Rear and Side Walls




Single Unit—High Rear and Side Walls with Building Overhang



Single Unit—High Front and Rear Walls with Building Overhang and No Side Walls



Single Unit—High Rear Wall and Low Front Wall with Building Overhang and No Side Walls



# CLEARANCES

## Outdoor Unit

### Note:

- Installation clearances must comply with local building codes.
- All figures not to scale.

### Legend


LR = Rear wall height

LF = Front wall height

H = Unit height

Figure 52: Proper Outdoor Unit Placement and Clearances, continued.

Side by Side—High Rear and Side Walls with Building Overhang



Side by Side—High Rear and Front Walls with Building Overhang






Figure 53: Proper Outdoor Unit Placement and Clearances, continued.


Single Row Units—High Rear Wall and Low Front Wall with No Side Walls or Overhang




Side by Side—High Front Wall with Building Overhang and No Side or Rear Walls




Side by Side—High Rear Wall and Low Front Wall with No Side Walls




Double Row Units—Low Rear and Front Walls with No Side Walls or Overhang



Side by Side—High Front and Rear Walls with No Side Walls



Side by Side—High Rear Wall and Low Front Wall with Building Overhang and No Side Walls



# INSTALLING OUTDOOR UNITS INDOORS

## Installing Outdoor Units Indoors

LG outdoor units are engineered to be mounted outdoors and include technology designed to minimize the negative effects of winter weather's freezing rain, sleet, and snow. Some building projects, however, necessitate placing the HVAC outdoor units indoors:

- Lack of ground space.
- Lack of an appropriate outdoor location that meets system design requirements.
- When mounting on the roof is not an option due to a lack of roof space.
- Roof warranty will be voided if mechanical equipment is placed on the membrane.
- On retrofit projects, a former chiller / boiler / air handler equipment room, mechanical area, or penthouse already exists.
- Where a project has vertical, self-contained VAV air handlers on each floor (in lieu of a centralized mechanical room).
- To curtail the potential need for redundant zone heating devices such as wall-fin radiators or duct heaters.
- In extremely cold environments where there is a significant amount of run-time at temperatures well below freezing outside the outdoor unit ambient air temperature range published in this engineering manual.

### Benefits of Installing Outdoor Units Indoors

- Shelters the outdoor unit from direct exposure to prevailing winds that decrease the heating capability of the outdoor unit.
- Protects equipment from freezing precipitation and / or potential ice build-up that could hinder unit operation.
- Maintains coil heat transfer efficiency by reducing the number of and shortening the cycle time for defrost operation.
- Easier maintenance and servicing during inclement weather.
- When mounted in a fully enclosed space, limiting the ambient air temperature may allow the system designer to eliminate oversizing the outdoor unit to compensate for loss of capacity at low ambient temperatures.
- May also curtail the need to provide inefficient redundant zone heating devices such as wall-fin radiators and second-stage ancillary heating devices.

### Design Considerations Include:

- Enclosure types and elements such as louvers, rain hoods, dampers and controls, heating methods and sizing of heating devices
- Heating strategies
- Duct design
- Condensate handling

### General Guidelines

- Follow ASHRAE 62.1 design guidelines.
- Depending on the project / application, a roof over the outdoor units in combination with a wind break may be all that is necessary.
- Consider the potential for snow accumulation near louvers / roof openings. Outside air intakes and discharge ducts/louvers should be engineered to clear anticipated snow accumulation levels by at least one (1) foot.
- In situations where operation is anticipated at temperatures of -13°F and lower, ancillary heat should be provided to heat the outdoor unit coils to assure continuous compressor operation and heating.

It may be necessary to use an air guide accessory to prevent discharge air from short-cycling back to the coil inlet.

- Another option is to field manufacture ductwork and mount on top of the unit to encompass the outdoor unit fan discharge and connect to the exterior discharge grille on the building.
- Avoid using a single duct on multi-fan units to prevent short cycling. Provide a dedicated duct for each outdoor unit fan discharge.
- Consider the direction of prevailing winds and opening placement. If possible, locate inlet openings upwind of discharge openings and other exhaust outlets.
- When inlet and outlet openings are placed on the same wall, minimum distance between the two openings should be approximately three (3) feet (minimum distance varies significantly with variations in outlet opening face velocity).
- If roof-mounted ventilation openings are used, strategically locate the inlet ventilation opening(s) upwind of the outlet opening(s).
- Discharge and supply ductwork should be designed to avoid weather related long periods of water entrainment and the potential for microbial growth.

# INSTALLING OUTDOOR UNITS INDOORS

---

Provide a means to drain the condensate generated during heating mode and defrost cycle in addition to rainwater that infiltrates the inlet louver enclosed area.

- Install a field-provided drain pan under the outdoor units and provide a path to a nearby floor drain.
- If the ambient air temperature is expected to drop below 32°F in the enclosure, heat the bottom surface of the pan, drain line, and floor drain so that the condensate does not freeze before reaching the drain.

Allow for ventilation intake and exhaust air based on maximum outdoor unit fan capacity.

- Select the size, type and orientation of architectural louvers with adequate "net free area" face velocity to ensure the total external static pressure from the outdoor unit fan does not exceed design limitations (see specification data tables).
- ⚠ No obstructions should be placed in front of the louver that could hamper the free flow (throw) of air.
- Roof top openings and / or discharge and supply louvers should be equipped with screens to prevent bird and insect infiltration.

As always, the best solution for each project balances acceptable heating performance (considering local weather conditions), capital costs, life cycle energy consumption, and limitations set forth by local building codes.

# REFRIGERANT PIPING DESIGN

## Design Guideline Summary

### Device Connection Limitations


A single-zone system consists of one outdoor unit and one indoor unit. One of the most critical elements of a single-zone system is the refrigerant piping. The table below lists pipe length limits that must be followed in the design of a single-zone Vertical Air Handling Unit refrigerant pipe system.

Table 47: Single-Zone Vertical Air Handling Unit Refrigerant Piping System Limitations.

| System Model Name                                                    |                                                       | LV180HV4, LV240HV4 | LV360HV4, LV480HV, LV488HV |
|----------------------------------------------------------------------|-------------------------------------------------------|--------------------|----------------------------|
| Pipe Length<br>(ELF = Equivalent Length of Pipe in Feet)             | Longest total equivalent piping length                | 164 feet           | 246 feet                   |
|                                                                      | Shortest total equivalent piping length               | 6.6 feet           | 6.6 feet                   |
|                                                                      | Distance between fittings and indoor or outdoor units | ≥20 inches         | ≥20 inches                 |
|                                                                      | No additional refrigerant                             | 24.6 feet          | 24.6 feet                  |
| Elevation<br>(All Elevation Limitations are Measured in Actual Feet) | If outdoor unit is above indoor unit                  | 98 feet            | 98 feet                    |
|                                                                      | If outdoor unit is below indoor unit                  | 98 feet            | 98 feet                    |
| Additional Refrigerant Needed (oz/ft)                                |                                                       | 0.43               | 0.43                       |

### System Layout

Figure 54: Typical LV180HV4 and LV240HV4 System Layout.




# REFRIGERANT PIPING DESIGN

## Design Guideline Summary

### System Layout

Figure 55: Typical LV360HV4, LV480HV and LV488HV System Layout.



# ACRONYMS

Table 48: Table of Acronyms.

|        |                                                                            |           |                                                   |
|--------|----------------------------------------------------------------------------|-----------|---------------------------------------------------|
| ABS    | Acrylonitrile Butadiene Styrene                                            | kW        | Kilo Watts                                        |
| AC     | Air Conditioner                                                            | LED       | Light Emitting Diode                              |
| ACP    | Advanced Control Platform                                                  | LEED      | Leadership in Energy and Environmental Design     |
| ASHRAE | American Society of Heating, Refrigeration, and Air-Conditioning Engineers | MBh       | Thousands BTUs per hour                           |
| AWG    | American Wire Gauge                                                        | MCA       | Maximum Circuit Ampacity                          |
| BLDC   | Brushless Digitally Controlled                                             | MOP       | Maximum overcurrent Protection                    |
| Btu/h  | British Thermal Units per hour                                             | MSC       | Maximum Starting Current                          |
| BUS    | Binary Unit System                                                         | NC        | Noise Criterion (regarding Sound Pressure Levels) |
| CFM    | Cubic Feet per Minute                                                      |           | New Construction (LEED Related)                   |
| DB     | Dry Bulb                                                                   |           | Normally Closed                                   |
| dB(A)  | Decibels with "A" frequency weighting                                      | NEC       | National Electrical Code                          |
| DDOAS  | Decoupled Dedicated Outdoor Air System                                     | No.       | Number                                            |
| DI     | Digital Input                                                              | ODU       | Outdoor Unit                                      |
| DFS    | Duct Free Split                                                            | PCB       | Printed Circuit Board                             |
| DO     | Digital output                                                             | PCM       | Pre-Coated Metal                                  |
| DPST   | Double-Pole Single-Throw (switch)                                          | PDI       | Power Distribution Indicator                      |
| EEV    | Electronic Expansion Valve                                                 | PI        | Power Input                                       |
| ELF    | Equivalent Length in Feet                                                  | PR        | Prerequisite (LEED Related)                       |
| ETL    | Electronic Testing Laboratories                                            | PVC       | Polyvinyl Chloride                                |
| H/M/L  | High/Medium/Low                                                            | SW or S/W | Switch                                            |
| HIPS   | High Impact Polystyrene                                                    | USB       | Universal Serial BUS                              |
| HVAC   | Heating, Ventilation and Air Conditioning                                  | VAC       | Voltage Alternating Current                       |
| ID     | Innovations in Design (LEED Related)                                       | VRF       | Variable Refrigerant Flow                         |
| IDU    | Indoor Unit                                                                | WB        | Wet Bulb                                          |
| ISO    | International organization for Standardization                             |           |                                                   |



*Inverter*



**LG**

Life's Good

LG Electronics, U.S.A., Inc.  
Air Conditioning Technologies  
4300 North Point Parkway  
Alpharetta, Georgia 30022  
[www.lghvac.com](http://www.lghvac.com)

LG Electronics Commercial Products Support  
1-888-865-3026 USA  
Follow the prompts for commercial A/C products.

New issue: EM\_SZ\_Vertical\_Air\_Handling\_Unit\_09\_17