Job Name/Location: Tag No.:

Date:	For:	File	Resubmit
PO No.:		Approval	Other

Architect: GC:
Engr: Mech:

Rep:

mpany) (Project Manager)

# PRHR023A Multi V™ Heat Recovery Unit Two (2) Port





#### Performance:

Maximum Port Capacity Btu/h (each port) <sup>1</sup>	60,000
Maximum Unit Capacity Btu/h (sum of ports)	120,000
Number of Indoor Unit Ports	2
Max. Connectible Number of Indoor Units	16
Max. Connectible Number of Indoor Units per	8
Branch Power Input <sup>2</sup>	
Cooling	39.8
Heating	37.2

## Refrigerant Piping:3

Port Liquid Line (in., O.D.)	3/8
Port Vapor Line (in., O.D.)	5/8
System Liquid Line (in., O.D.)	3/8
System Vapor Line High (in., O.D.)	3/4
System Vapor Line Low (in., O.D.)	7/8

# Power Supp

Power Supply (V/Hz/Ø)	208-230/60/1
Rated Amps	0.06

#### **Unit Data:**

Refrigerant Type	R410A
Refrigerant Control	EEV
Sound Pressure	
Cooling Mode dB(A)	31
Heating Mode dB(A)	31
Simultaneous dB(A)	38
Changeover Cooling to Heating	33
Changeover Heating to Cooling	38
Unit Net Weight (lbs.)	33
Unit Shipping Weight (lbs.)	46

### **Features:**

- Allows connected indoor units to be in cooling or heating mode simultaneously.
- Internal components are insulated.
  - External casing insulation is not needed.3
  - Condensate drain not needed.
- Series or parallel connection with additional heat recovery units.
- Flexible placement for service access or pipe routing.
- Access panels:
  - Top panel for EEV heads.
  - Rear panel for control access.
  - Bottom panel for refrigerant circuit.

## Notes:

- 1. Each port can allow up to 8 indoor units with a maximum capacity of 60 MBh per port.
- 2. Power wiring is field provided, and must comply with the applicable local and national codes.
- 3. All refrigerant piping requires insulation.
- 4. Communication cable between Master outdoor units to indoor units / heat recovery units to be 18 AWG, 2-conductor, twisted, stranded, shielded. Ensure the communication cable shield is properly grounded to the Master outdoor unit chassis only. Do not ground the outdoor unit to indoor units / heat recovery units communication cable at any other point. Wiring must comply with all applicable local and national codes.
- 5. Kit components must be kept dry and free of debris before installation.
- 6. This unit comes with a dry nitrogen charge.
- 7. Must follow installation instructions in the applicable LG installation manual.



Job Na	me/Loc	ation:
--------	--------	--------

# PRHR023A

Multi V™ Heat Recovery Unit

Two (2) Port





ag No.:	
ate.	


PO No.: \_


19-1/8"	8-5/8"	18-15/16"	5-15/16"	6-15/16"	3/4"	5-15/16"	2-3/16"	5-3/4"	4-9/16"	2-5/16"	8-9/16"	6-3/16"	3-9/16"	p,*	4-15/16"	12-1/4"	1-1/2"	19-11/16"
>	I	D	17	L2	L3	۲4	L5	97	۲٦	L8	67	L10	L11	L12	M	MP	M3	Δ

Centrol box	Liquid pipe to Indoor unit	Gas pipe to Indoor unit	Low pressure gas pape	Liquid pipe to dutdoor unit	High pressure gas pipe	Part Name
ш	æ	4	es	84	-	횽









installed in compliance with the installation accordance with the local

[Unit: inch]