Job Name/Location:					Tag #:		
Date:		For:	File	Resubmit			
PO No.:			Approval	Other			
Architect:	GC:					фu	
Engr:	Mech	n:					\$ DIV
Rep:	(Project N	lanager)					

# LSN180HSV5

Multi F Wall Mounted DUAL COOL Indoor Unit 18,000 Btu/h



#### Performance:

Nominal Cooling Capacity (Btu/h)	18,000
Nominal Heating Capacity (Btu/h)	21,600

Cooling Nominal Test Conditions: Indoor: 80°F DB / 67°F WB Outdoor: 95°F DB / 75°F WB

Heating Nominal Test Conditions: Indoor: 70°F DB / 60°F WB Outdoor: 47°F DB / 43°F WB

### **Electrical:**

Power Supply (V¹/Hz/Ø)	208-230/60/1
Rated Amps (A)	0.4

## Piping:

Installed Liquid Pipe (in., O.D.)	ø1/4
Installed Vapor Pipe (in., O.D.)	ø1/2
Liquid Connection (in., O.D.)	ø3/8
Vapor Connection (in., O.D.)	ø5/8
Drain (in., O.D. / I.D.)	27/32,5/8
Temperature Sensor	Thermistor

#### **Controls Features:**

- 4-Way auto swing24-Hour on/off timerAuto operation

- Auto restartChaos wind
- Inverter (variable speed fan)
- Jet cool/Jet heat3M Micro Dust Filter

- Self-cleaning indoor coil
   Sleep mode
   Condensate sensor connection
   Built-in Wi-Fi via Smart ThinQ app
- Compatible with Single Zone HSV5 Outdoor Units

## **Entering Mixed Air:**

Cooling (°F WB)	57 ~ 77
Heating (°F DB)	59 ~ 81

### **Unit Data:**

Refrigerant Type	R410A
Refrigerant Control	EEV
Sound Pressure (H/M/L) (±3 dB[A]) <sup>2</sup>	44 / 38 / 34
Primary Filter	Washable Pre-filter
Secondary Filter	3M Micro Dust
Net Weight (lbs.)	25.6
Shipping Weight (lbs.)	32.2
Shipping Weight (183.)	32.2

#### Fan:

Туре	Cross Flow
Quantity	1
Motor/Drive	Brushless Digitally Controlled/Direct
Air Flow H/M/L (CFM)	558 / 438 / 353

# Notes:

- NOTES:

  1. Acceptable operating voltage: 187V-253V.
  2. Sound Pressure levels are tested in an anechoic chamber under ISO Standard 3745.
  3. See Engineering Manual for sensible and latent capacities.
  4. All communication / connection (power) cable from the outdoor unit to the indoor unit is field supplied and must be a minimum of four-conductor, 18 AWG, stranded, shielded or unshielded (if shielded, it must be grounded to the chassis of the outdoor unit only), and must comply with applicable local and national codes.
  5. Power wiring cable size must comply with applicable local and national code.
  6. The indoor unit comes with a dry helium charge.
  7. Corresponding refrigerant piping length is in accordance with standard length of each outdoor unit and the level difference is 0 ft. All capacities are net with a combination ratio between 95 105%.
  8. Must follow installation in instructions in the applicable LG installation manual.

- 8. Must follow installation instructions in the applicable LG installation manual.
  9. Multi compatible 18k IDUs include socket adapters for refrigerant pipe connections with Multi F systems.

## **Included Accessories:**

• Wireless Remote Controller — PWLSSB21H

### **Optional Accessories:**

☐ MultiSITE™ CRC2 - PREMTBVC2 ☐ Dry Contact 3rd Party Controller - PDRYCB320 ☐ Cable Extension Kit - PZCWRC1 ☐ Aux Heater Relay Kit - PRARS1 Programable Remote Contoller - PREMTB100 ☐ Delux Remote Contoller - PREMTB200

☐ Group Controller Cable Kit - PZCWRCG3









# LSN180HSV5

Multi F Wall Mounted DUAL COOL Indoor Unit 18,000 Btu/h



Tag No.: \_\_\_\_\_\_

Date: \_\_\_\_\_

PO No.: \_\_\_\_\_

