(Project Manager)


Date:	For:	File	Resubmit
PO No.:		Approval	Other
Architect:	GC:		
Engr:	Mech:		
Ren·			





PQRCVSLO



PQRCVSL0QW







- 1 Operation Indication Screen
- 2 Set Temperature Button
- 3 Fan Speed Button
- 4 On/Off Button
- 5 Operation Mode Selection Button
- 6 Wireless Remote Controller Receiver
- 7 Air Flow Button1
- 8 Sub Function Button¹
- 9 Function Setting Button
- 10 Ventilation Button¹ (Only applicable to LG ventilation products which are not currently available in the U.S.)
- 11 Reservation
- 12 Up, Down, Left, Right Menu Navigation Buttons
- 13 Room Temperature Button
- 14 Setting/Cancel Button
- 15 Exit Button

PQRCVSLO (QW)

7 Day Programmable Controller



Unit Data:

Max Number of Indoor Units (Group Control) Temperature Value Fahrenheit (1° Increments)/Celsius 4-3/4" L x 4-3/4" W x 5/8" H **Dimensions** Weight 0.57 lbs

Temperature Value depends on equipment.

Operating Range:

Cooling (°F)	64-86
Heating (°F)	60-86

Communications Cabling Specifications (V-Net):

Туре	Included
Length	33 feet

Communication cable can be extended to a maximum of 164 feet by using the Wired Zone Controller Extension Cable - PZCWRC1 (maximum 4 kits). Field splicing is prohibited.

Standard Features:

- •Unit Operation On/Off
- Mode Selection Cool/Heat/Dry/Fan/Auto
- Fan Speed Selection
- •Air Flow Direction1
- •Static Pressure Setting
- •Child Lock
- •LED Indicator for operating status
- •Master/Slave Setting for Multiple Controller Installation
- Programmable Patterns Simple/Sleep/On/Off/Weekly/Holiday
- •Seven Day Programmable Schedule
- •Maximum two schedule events per day or 14 events per week²
- Clock
- BLU Backlighting
- Power Failure Compensation (up to 3 hours)
- Function setting for plasma filter, electric heat, humidifier, elevation grille, ventilation kit and auxiliary heat option1

Notes:

- 1. Available with indoor units equipped for this function
- 2. Each event can be assigned an operating state (on/off) and temperature setpoint value. Operating mode (cool, heat, dry, fan, auto) cannot be linked to a programmed event.
- Must follow installation instructions in the applicable LG installation manual.

Optional Accessories:

- 33-foot Extension Cable Assembly (PZCWRC1)
- Wireless Remote Controller (PQWRHDF0)