Job Name/Location:

Date:
PO No.:

Architect:

Engr:

Rep:
(Company)

(Project Manager)

Tag #:

For: File Resubmit
Approval Other_____
Approval Other_____

ARNU243SKS4

Multi V™ Standard Wall Mounted Unit 24,200 Btu/h Indoor Unit

Performance:

Total Cooling Capacity (Btu/h) ¹	24,200
Heating Capacity (Btu/h) ¹	25,600
Max Power Input (W) ²	53
H / M / L Power Input at Factory	55
Default (W)	39 / 26 / 16

Rated capacity is certified under AHRI Standard 1230. Ratings are subject to change without notice. Current certified ratings are available at www.ahridirectory.org.

Electrical:

Power Supply (V/Hz/Ø)	208-230 / 60 / 1
Rated Amps	0.52

Piping:

Refrigerant	
Liquid Line (in., O.D.)	3/8 Flare
Vapor Line (in., O.D.)	5/8 Flare
Condensate	
Condensate Line (in., I.D.)	5/8
Factory Installed Pump	No

Controls Features:

- Auto changeover (Heat Recovery only)
- Auto operation
- Auto restart
- Dual thermistor control
- Dual setpoint control
- Multiple auxillary heater applications

- Timer (on/off)
- Weekly schedule
- Auto direction/
- swing (up/down)
- Fan speed control
- Jet cool (fast cooling)
- Filter life display
- Child lock
- Group control

- Hot start
- Self diagnostics
- External on/off control
- Wi-Fi (built-in)
- Auto Fan
- Leak Detection

Ontional Accessories

Optional Accessories:
☐ Wireless Remote Controller - PWLSSB21H
☐ MultiSITE™ CRC2 Controller - PREMTBVC2
☐ MultiSITE™ CRC2+ Controller - PREMTBVC3
☐ MultiSITE™ CRC2+Z Controller - PREMTBVC4
☐ Simple Remote Controller - PREMTC00U
☐ Standard III Remote Controller – PREMTB100
☐ Standard III Remote Controller – PREMTBB10
☐ Remote Temperature Button Sensor - ZRTBS01
☐ Simple Dry Contact (1 contact, 24 VAC external power) - PDRYCB100
☐ Dry Contact for Third Party Thermostat - PDRYCB320
☐ Dry Contact for Economizer - PDRYCB400
☐ Auxillary Heater Kit - PRARS1



Unit Data:

R410A
EEV
41 / 34
ashable
28.7
31.7

Fan:

Туре	Cross Flow
Quantity	1
Motor/Drive	Brushless Digitally Controlled/Direct
Motor Quantity	1
Air Flow Rate H / M / L (CFM)	537 / 449 /371

Notes:

- 1. See Engineering Manual for sensible and latent capacities.
- 2. Max. power input is rated at maximum setting value.
- 3. Sound Pressure levels are tested in an anechoic chamber under ISO Standard 3745.
- 4. All communication cable must be minimum 18 AWG, 2-conductor, twisted, stranded, shielded and must comply with applicable local and national codes. Ensure the communication cable is properly grounded at the main outdoor unit only. Do not ground the outdoor unit to indoor units / heat recovery units communication cable at any other point. Wiring must comply with all applicable local and national codes.
- 5. Power wiring is field provided and must comply with the applicable local and national codes.
- 6. This unit comes with a dry nitrogen charge.
- 7. All capacities are net with a combination ratio between 95 105%.
- 8. Must follow installation instructions in the applicable LG installation manual.



ARNU243SKS4

Multi V™ Standard Wall Mounted Unit

24,200 Btu/h Indoor Unit





